

Directional Median Installation on US 49 at Siloam Road and a Traffic Signal at SR 149, known as Federal Aid Project No. HSIP-0008-02 (123) / 109119301 in Simpson County.					T. L. Wallace Construction, Inc.	Hemphill Construction Company, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,923,176.89					\$1,838,543.45	\$2,575,423.05	
Ref#	Item	Item Description	Item Qnty	Units	1	2	
0010	201-C002	Random Clearing and Grubbing	1.000	ACRE	15,000.00	10,000.00	
0020	202-B007	Removal of Asphalt Pavement, All Depths	3,455.000	SY	9.70	40.00	
0030	202-B052	Removal of Concrete Driveways, All Depths	335.000	SY	36.00	35.00	
0040	202-B089	Removal of Curb &/or Curb and Gutter, All Types	80.000	LF	14.50	30.00	
0050	202-B098	Removal of Debris and Sand From Box Culvert, Less Than 6-foot Width	148.000	LF	50.00	150.00	
0060	202-B114	Removal of Debris and Sand From Pipe, All Sizes	287.000	LF	50.00	50.00	
0070	202-B191	Removal of Pipe, 8" And Above	136.000	LF	37.25	75.00	
0080	202-B219	Removal of Sign, Ground Mounted with Posts	5.000	EA	415.50	120.00	
0090	202-B240	Removal of Traffic Stripe	14,233.000	LF	4.65	5.00	
0100	203-A001	Unclassified Excavation, FM, AH	1,911.000	CY	30.00	35.00	
0110	203-EX021	Borrow Excavation, AH, FME, Class B9-6	550.000	CY	30.00	50.00	
0120	206-A001	Structure Excavation	88.000	CY	34.75	20.00	
0130	209-A005	Geotextile Stabilization, Type V, Non-Woven	6,210.000	SY	4.15	6.50	
0140	213-C001	Superphosphate	7.000	TON	1,136.00	1,100.00	
0150	216-A001	Solid Sodding	221.000	SY	9.35	15.00	
0160	217-A001	Ditch Liner	35.000	SY	23.50	23.00	
0170	219-A001	Watering	4.000	KGAL	20.00	20.00	
0180	220-A001	Insect Pest Control	7.000	ACRE	30.00	30.00	
0190	221-A001	Concrete Paved Ditch	1.000	CY	3,000.00	1,500.00	
0200	223-A001	Mowing	28.000	ACRE	50.00	50.00	
0210	225-A001	Grassing	14.000	ACRE	1,165.00	1,100.00	
0220	225-B001	Agricultural Limestone	28.000	TON	122.25	120.00	
0230	225-C001	Mulch, Vegetative Mulch	28.000	TON	250.50	250.00	
0240	226-A001	Temporary Grassing	14.000	ACRE	1,107.00	1,000.00	
0250	237-A002	Wattles, 20"	209.000	LF	16.00	20.00	
0260	246-B002	Rockbags	240.000	LF	17.50	20.00	

Directional Median Installation on US 49 at Siloam Road and a Traffic Signal at SR 149, known as Federal Aid Project No. HSIP-0008-02 (123) / 109119301 in Simpson County.					T. L. Wallace Construction, Inc.	Hemphill Construction Company, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,923,176.89					\$1,838,543.45	\$2,575,423.05	
Ref#	Item	Item Description	Item Qnty	Units	1	2	
0270	247-A001	Temporary Stream Diversion	1.000	EA	1.00	7,500.00	
0280	249-A001	Riprap for Erosion Control	40.000	TON	100.00	150.00	
0290	249-B001	Remove and Reset Riprap	24.000	CY	36.75	85.00	
0300	304-D002	Granular Material, Crushed Stone	1,970.000	TON	84.50	125.00	
0310	406-D001	Fine Milling of Bituminous Pavement, All Depths	2,075.000	SY	12.25	13.00	
0320	407-A001	Asphalt for Tack Coat	220.000	GAL	4.65	6.00	
0330	503-C010	Saw Cut, Full Depth	160.000	LF	40.00	15.00	
0340	601-B001	Class "B" Structural Concrete, Minor Structures	10.000	CY	2,800.00	8,500.00	
0350	602-A001	Reinforcing Steel	426.000	LBS	2.75	2.00	
0360	603-CA011	18" Reinforced Concrete Pipe, Class III	72.000	LF	100.00	120.00	
0370	603-CA040	30" Reinforced Concrete Pipe, Class III	56.000	LF	140.00	150.00	
0380	603-CB003	18" Reinforced Concrete End Section	2.000	EA	1,500.00	950.00	
0390	603-CB005	30" Reinforced Concrete End Section	2.000	EA	2,000.00	1,400.00	
0400	603-CE039	73" x 45" Concrete Arch Pipe, Class A III	88.000	LF	500.00	450.00	
0410	603-CF009	73" x 45" Concrete Arch Pipe End Section	1.000	EA	6,460.00	5,000.00	
0420	604-B001	Gratings	250.000	LBS	4.65	10.00	
0430	609-D004	Combination Concrete Curb and Gutter Type 2 Modified	330.000	LF	67.00	80.00	
0440	614-B003	Concrete Driveway, With Reinforcement, 6-inch Thickness	350.000	SY	119.50	145.00	
0450	616-A001	Concrete Median and/or Island Pavement, 10-inch	20.000	SY	208.50	265.00	
0460	616-A004	Concrete Median and/or Island Pavement, 4-inch	110.000	SY	90.00	150.00	
0470	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	176.000	SF	10.50	15.00	
0480	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	940.000	SF	10.50	15.00	
0490	619-G4001	Barricades, Type III, Double Faced	36.000	LF	28.00	30.00	
0500	619-G4005	Barricades, Type III, Single Faced	618.000	LF	24.50	25.00	
0510	619-G4007	Barricades, Type III, Single Faced, Permanent, Red/White	30.000	LF	99.00	100.00	
0520	619-G5001	Free Standing Plastic Drums	39.000	EA	174.75	80.00	

Directional Median Installation on US 49 at Siloam Road and a Traffic Signal at SR 149, known as Federal Aid Project No. HSIP-0008-02 (123) / 109119301 in Simpson County.					T. L. Wallace Construction, Inc.	Hemphill Construction Company, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,923,176.89					\$1,838,543.45	\$2,575,423.05	
Ref#	Item	Item Description	Item Qnty	Units	1	2	
0530	619-G7001	Warning Lights, Type "B"	18.000	EA	75.75	1,800.00	
0532	620-A001	Mobilization	1.000	LS	185,000.00	280,000.00	
0540	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	111.000	SF	27.00	25.00	
0550	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	194.000	SF	29.25	28.00	
0560	630-A005	Standard Roadside Signs, Sheet Aluminum, 0.1" Thickness	123.000	SF	28.00	27.00	
0570	630-C001	Square Tube Posts, 4.0 lb/ft	16.000	LF	40.75	40.00	
0580	630-C005	Square Tube Posts, 2.0 lb/ft	507.000	LF	22.25	21.00	
0590	630-C1001	Square Post Inner Sleeve	64.000	LF	18.75	18.00	
0600	635-A059	Traffic Signal Head, Type 1	5.000	EA	1,264.00	1,050.00	
0610	635-A061	Traffic Signal Head, Type 2	1.000	EA	1,275.00	1,200.00	
0620	635-A070	Traffic Signal Head, Type 3	1.000	EA	1,910.00	1,600.00	
0630	638-A003	Flashing Assembly, Be Prepared to Stop When Flashing	2.000	EA	5,385.00	5,460.00	
0640	699-A001	Roadway Construction Stakes	1.000	LS	28,000.00	33,620.00	
0650	815-A002	Loose Riprap, Size 100	120.000	TON	100.00	140.00	
0660	815-E001	Geotextile under Riprap	210.000	SY	4.15	5.00	
0670	907-234-A001	Temporary Silt Fence	2,800.000	LF	4.40	4.50	
0680	907-234-D001	Inlet Siltation Guard	2.000	EA	757.00	770.00	
0690	907-234-E001	Reset Inlet Siltation Guard	2.000	EA	407.50	400.00	
0700	907-403-A001	12.5-mm, HT, Asphalt Pavement	360.000	TON	170.75	175.00	
0710	907-403-A003	12.5-mm, ST, Asphalt Pavement	50.000	TON	232.75	400.00	
0720	907-403-A006	19-mm, ST, Asphalt Pavement	560.000	TON	154.25	225.00	
0730	907-403-A013	9.5-mm, HT, Asphalt Pavement	400.000	TON	171.50	200.00	
0740	907-618-A001	Maintenance of Traffic	1.000	LS	130,000.00	350,000.00	
0750	907-626-A008	6" Thermoplastic Double Drop Traffic Stripe, Skip White	4,471.000	LF	1.00	0.90	
0760	907-626-B003	6" Thermoplastic Double Drop Traffic Stripe, Continuous White	2,541.000	LF	1.90	1.70	
0770	907-626-E004	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	3,147.000	LF	1.80	1.60	

Directional Median Installation on US 49 at Siloam Road and a Traffic Signal at SR 149, known as Federal Aid Project No. HSIP-0008-02 (123) / 109119301 in Simpson County.					T. L. Wallace Construction, Inc.	Hemphill Construction Company, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,923,176.89					\$1,838,543.45	\$2,575,423.05	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0780	907-626-G006	Thermoplastic Double Drop Detail Stripe, White	5,433.000	LF	5.25	4.75	
0790	907-626-G007	Thermoplastic Double Drop Detail Stripe, Yellow	3,497.000	LF	5.25	4.75	
0800	907-626-H006	Thermoplastic Double Drop Legend, White	372.000	SF	10.50	9.50	
0810	907-626-H007	Thermoplastic Double Drop Legend, White	510.000	LF	8.15	7.40	
0820	907-627-J001	Two-Way Clear Reflective High Performance Raised Markers	47.000	EA	14.00	12.60	
0830	907-627-K001	Red-Clear Reflective High Performance Raised Markers	129.000	EA	14.00	12.60	
0840	907-627-L001	Two-Way Yellow Reflective High Performance Raised Markers	62.000	EA	14.00	12.60	
0850	907-630-O008	Remove and Reset Signs, Post Mounted	2.000	EA	1,107.00	1,175.00	
0860	907-632-A007	Solid State Traffic Cabinet Assembly, Type III Cabinet, Type 1 Controller	1.000	EA	24,300.00	23,100.00	
0870	907-632-J001	Power Service Pedestal	1.000	EA	6,229.00	4,200.00	
0880	907-634-A050	Traffic Signal Equipment Pole, Type II(L), 30' Shaft, 70' Arm	1.000	EA	34,000.00	31,500.00	
0890	907-634-A280	Traffic Signal Equipment Pole, Type III(L), 30' Shaft, 60' & 60' Arm	1.000	EA	51,100.00	47,250.00	
0900	907-634-B001	Traffic Signal Equipment Pole Shaft Extension, 10'	1.000	EA	1,922.00	1,260.00	
0910	907-634-C001	Pole Foundations, Class "B" Concrete	7.000	CY	1,456.00	1,050.00	
0920	907-636-B003	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 10, 2 Conductor	545.000	LF	3.50	1.05	
0930	907-636-B013	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 14, 4 Conductor	1,525.000	LF	3.50	3.15	
0940	907-636-B016	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 14, 8 Conductor	365.000	LF	4.65	3.15	
0950	907-636-B028	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 8, 3 Conductor	135.000	LF	4.65	16.00	
0960	907-636-C015	Electric Cable, Aerial Supported, IMSA 20-1, AWG 8, 3 Conductor	6.000	LF	10.25	31.50	
0970	907-636-D001	Electric Cable, Aerial Supported in Conduit, IMSA 20-1, AWG 10, 2 Conductor	16.000	LF	7.00	31.50	
0980	907-636-D005	Electric Cable, Aerial Supported in Conduit, IMSA 20-1, AWG 14, 4 Conductor	32.000	LF	7.00	1.05	
0990	907-636-D008	Electric Cable, Aerial Supported in Conduit, IMSA 20-1, AWG 14, 8 Conductor	164.000	LF	5.85	3.15	
1000	907-637-A002	Pullbox Enclosure, Type 2	8.000	EA	1,392.00	1,155.00	
1010	907-637-A003	Pullbox Enclosure, Type 3	1.000	EA	2,195.00	1,470.00	
1020	907-637-C026	Traffic Signal Conduit, Underground, Type 4, 1"	30.000	LF	11.75	10.50	
1030	907-637-C028	Traffic Signal Conduit, Underground, Type 4, 2"	1,465.000	LF	14.00	12.60	

Directional Median Installation on US 49 at Siloam Road and a Traffic Signal at SR 149, known as Federal Aid Project No. HSIP-0008-02 (123) / 109119301 in Simpson County.					T. L. Wallace Construction, Inc.	Hemphill Construction Company, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,923,176.89					\$1,838,543.45	\$2,575,423.05	
Ref#	Item	Item Description	Item Qty	Units	1	2	
1040	907-637-C030	Traffic Signal Conduit, Underground, Type 4, 3"	10.000	LF	17.50	20.00	
1050	907-637-D003	Traffic Signal Conduit, Underground Drilled or Jacked, Rolled Pipe, 3"	260.000	LF	33.00	20.00	
1060	907-641-A002	Signal Stop Bar Radar Vehicle Detection Sensor, Type 2	2.000	EA	8,296.00	7,500.00	
1070	907-641-B002	Signal Advanced Radar Vehicle Detection Sensor, Type 2	2.000	EA	8,034.00	8,000.00	
1080	907-641-D001	Radar Vehicle Detection Cable	1,360.000	LF	4.10	4.20	
1090	907-641-F002	Signal Radar Vehicle Detection Processor, Type 2	2.000	EA	7,423.00	10.50	
1100	907-650-A004	On Street Video Equipment, PTZ Type, Signal Monitoring	1.000	EA	3,127.00	3,500.00	
1110	907-662-D002	Radio Interconnect, Broadband, Short Range	1.000	EA	5,921.00	5,900.00	
1120	907-663-A006	Network Switch, Type F	1.000	EA	12,300.00	5,250.00	
1130	304-F001	3/4" and Down Crushed Stone Base OR	1,350.000	TON			
1140	304-F002	Size 610 Crushed Stone Base OR	1,350.000	TON		125.00	
1150	304-F003	Size 825B Crushed Stone Base	1,350.000	TON	84.50		