

Call 17 Mill & Overlay approximately 3 miles of US 98 from 400 feet west of Weathersby Drive to the Lamar / Forrest County Line, & Striping & Raised Pavement Markers on MS 198 from the Lamar / Forrest County Line to US 49, known as State Project Nos. SP-0014-02(091) / 108952301 & SP-0014-02(099) / 108952302 in Lamar & Forrest Counties.

Q1. Are the Type 1 Video Vehicle Detection 1A & 1B eligible for substitution of the Signal Stop Bar & Advance Radar Vehicle Detection Type 2 Sensor for this project. The City of Hattiesburg is running multiple of the Currux videos and none of the Wavetronix.

A1. ~~Yes.~~ **Revised Answer:** Bidders are advised to bid as per the Contract Documents.

Q2. Under Item No. 413-D002: Cleaning and Filling Joints, what type sealant is required? Silicone or Hot pour?

A2. Hot pour is required.

Q3. Will the outside continuous turn lane that runs from I-59 to the EOP be overlaid with SMA 9.5-mm?

A3. Yes.