

**Call 15 Mill & Overlay approximately 9 miles of SR 346 from the beginning of State Maintenance to SR 15, known as State Project No. SP-0858-00(017) / 108919301 in Pontotoc County.**

- Q1. Will the road be able to be closed for the removal and installation of pipes? Or install half a lane at a time?
- A1. Pipe will be installed one lane at a time using lane closures.
- Q2. Are there any digout stations for Sheet TS-1? The ones listed on Sheet TS-2 do not add up to the Pay Item quantities.
- A2. The quantity includes the digout locations shown in the plans, removal needed for pipe removal and replacement as well as additional quantity to be used as directed by the Engineer. Bidders are advised to bid as per the Contract Documents.
- Q3. Can the Department provide a schedule how much asphalt will be used for patching, leveling, mainline and County roads?
- A3. The estimated breakdown is as follows: 12,590 tons for mainline, 360 tons for county roads, 687 tons for driveways, 980 tons for digouts and 2,500 tons for pre-leveling.
- Q4. Does the existing stripe need to be removed prior to scrub sealing operations?
- A4. No removal of stripe will be required prior to scrub sealing.