

Mill & Overlay approximately 4.3 miles of I-55 Carroll Co from the Montgomery County Line to the Carroll County Line, known as Federal Aid Project No. IM-0055-03(097) / 108590301 in Carroll County and No. IM-0055-03(097) / 108590302 in Montgomery County.					Lehman-Roberts Company		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$12,972,228.44					\$13,755,607.25		
Ref#	Item	Item Description	Item Qnty	Units	1		
0010	201-D001	Random Clearing	329.000	STA	1,300.00		
0020	202-B069	Removal of Concrete Pavement w/ Variable Depth Overlay	44.000	SY	125.00		
0030	202-B117	Removal of Delineator, All Types	4.000	EA	110.00		
0040	202-B158	Removal of Guard Rail, Including Rails, Posts and Terminal Ends	48,168.000	LF	3.25		
0050	202-B213	Removal of Sign	16.000	EA	97.00		
0060	202-B215	Removal of Sign Including Post & Footing	12.000	EA	97.00		
0070	203-G001	Excess Excavation, FM, AH	3.000	CY	55.00		
0080	304-B004	Granular Material, Class 5, Group D	17,625.000	TON	48.50		
0090	304-B005	Granular Material, Class 5, Group E	4,575.000	TON	70.50		
0100	406-D001	Fine Milling of Bituminous Pavement, All Depths	330,036.000	SY	3.30		
0110	407-A001	Asphalt for Tack Coat	32,760.000	GAL	3.75		
0120	413-B001	Cleaning and Sealing Joints	832.000	LF	10.25		
0130	423-A001	Rumble Strips, Ground In	23.000	MI	1,200.00		
0140	503-C010	Saw Cut, Full Depth	180.000	LF	15.00		
0150	606-B002	Guard Rail, Class A, Type 1, 'W' Beam	45,075.000	LF	26.75		
0160	606-B010	Guard Rail, Class A, Type 1, Thrie Beam	250.000	LF	38.50		
0170	606-B013	Guard Rail, Class A, Type 1, Thrie Beam, Transition Section	118.000	LF	48.00		
0180	606-C003	Guard Rail, Cable Anchor, Type 1	74.000	EA	800.00		
0190	606-E005	Guard Rail, Terminal End Section, Flared	74.000	EA	2,700.00		
0200	618-B001	Additional Construction Signs	2.000	SF	10.00		
0210	619-A1001	Temporary Traffic Stripe, Continuous White	40.000	MI	2,100.00		
0220	619-A2001	Temporary Traffic Stripe, Continuous Yellow	42.000	MI	2,100.00		
0230	619-A3001	Temporary Traffic Stripe, Skip White	42.000	MI	2,100.00		
0240	619-A5001	Temporary Traffic Stripe, Detail	39,231.000	LF	0.45		
0250	620-A001	Mobilization	1.000	LS	550,000.00		
0260	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	26.000	SF	23.50		

Mill & Overlay approximately 4.3 miles of I-55 Carroll Co from the Montgomery County Line to the Carroll County Line, known as Federal Aid Project No. IM-0055-03(097) / 108590301 in Carroll County and No. IM-0055-03(097) / 108590302 in Montgomery County.					Lehman-Roberts Company		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$12,972,228.44					\$13,755,607.25		
Ref#	Item	Item Description	Item Qnty	Units	1		
0270	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	228.000	SF	25.60		
0280	630-A005	Standard Roadside Signs, Sheet Aluminum, 0.1" Thickness	114.000	SF	24.50		
0290	630-C001	Square Tube Posts, 4.0 lb/ft	15.000	LF	39.50		
0300	630-C005	Square Tube Posts, 2.0 lb/ft	210.000	LF	19.25		
0310	630-F006	Delineators, Guard Rail, White	643.000	EA	23.50		
0320	630-F007	Delineators, Guard Rail, Yellow	405.000	EA	23.50		
0330	630-F010	Delineators, Post Mounted, Double White	37.000	EA	65.00		
0340	630-F011	Delineators, Post Mounted, Double Yellow	2.000	EA	65.00		
0350	630-F012	Delineators, Post Mounted, Single White	28.000	EA	55.50		
0360	630-F013	Delineators, Post Mounted, Single Yellow	16.000	EA	55.50		
0370	815-A007	Loose Riprap, Size 300	2,425.000	TON	135.00		
0380	815-E001	Geotextile under Riprap	2,964.000	SY	8.00		
0390	907-402-A002	Open Graded Friction Course, 9.5-mm Mixture	12,750.000	TON	192.00		
0400	907-402-B001	Bituminous Tack Coat	23,405.000	GAL	4.25		
0410	907-403-A006	19-mm, ST, Asphalt Pavement	50.000	TON	300.00		
0420	907-403-A015	9.5-mm, ST, Asphalt Pavement	7,375.000	TON	152.00		
0430	907-403-S001	Joint Sealant	14.000	MI	1,500.00		
0440	907-405-A001	Stone Matrix Asphalt, 9.5 mm Mixture	19,800.000	TON	178.00		
0450	907-413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	96.000	LF	10.25		
0460	907-618-A001	Maintenance of Traffic	1.000	LS	450,000.00		
0470	907-619-E3001	Changeable Message Sign	2.000	EA	8,000.00		
0480	907-626-A007	6" Thermoplastic Double Drop Traffic Stripe, Skip White	14.000	MI	3,950.00		
0490	907-626-C012	6" Thermoplastic Double Drop Edge Stripe, Continuous White	14.000	MI	7,900.00		
0500	907-626-F003	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow	14.000	MI	7,900.00		
0510	907-626-G006	Thermoplastic Double Drop Detail Stripe, White	10,368.000	LF	3.10		
0520	907-626-G007	Thermoplastic Double Drop Detail Stripe, Yellow	2,709.000	LF	3.10		

Mill & Overlay approximately 4.3 miles of I-55 Carroll Co from the Montgomery County Line to the Carroll County Line, known as Federal Aid Project No. IM-0055-03(097) / 108590301 in Carroll County and No. IM-0055-03(097) / 108590302 in Montgomery County.					Lehman-Roberts Company		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$12,972,228.44					\$13,755,607.25		
Ref#	Item	Item Description	Item Qty	Units	1		
0530	907-627-K001	Red-Clear Reflective High Performance Raised Markers	1,297.000	EA	12.50		
0540	907-906001	Trainees	520.000	HRS	5.00		