

Call 09 Placement of Audible Stripe on MS 433 from Yazoo County Line to Ebenezer-Coxburg Road in Benton and from Old Highway 16 to the Holmes County Line, known as Federal Aid Project Nos. HRRR-1515-00(014) / 110035301,302 in Holmes and Yazoo Counties

- Q1. 1.) NTB No. 7359 Note 5 includes PROJECT CLEANUP as Incidental Work. Is this referring to construction debris only? 2.) NTB No. 5086 detail sheet Working Number TSS-2 Notes A & B state that the 36" Anchor and the OMNI Sleeve are absorbed. Working Number TSS-2 in NTB No. 7359 only calls for the OMNI Sleeve to be absorbed. Which is correct for this project? Will payment include the post length and the 36" anchor or only the post length?
- A1. 1.) Clean-up refers to removal of any vegetation, debris, or construction debris necessary for successful completion of the work detailed in this contract or any debris created while performing the work. This is not referring to the litter pick-up that is often in overlay contracts. 2.) The 36" anchor and the OMNI sleeve shall be considered absorbed.