

Mill & Overlay approximately 12.4 miles of SR 9 from SR 9W to the Pontotoc County Line, known as Federal Aid Project No. STP-0050-01(043) / 109755301 in Calhoun County.					Lehman-Roberts Company	APAC - Mississippi, Inc.	Cook & Son, LLC
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$6,949,232.45					\$7,568,195.94	IRREGULAR \$8,224,912.20	\$9,719,846.41
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0010	201-D001	Random Clearing	962.000	STA	1,100.00	1,097.25	1,713.10
0020	202-B007	Removal of Asphalt Pavement, All Depths	9,226.000	SY	42.30	35.00	23.62
0030	202-B158	Removal of Guard Rail, Including Rails, Posts and Terminal Ends	747.000	LF	9.25	8.00	8.00
0040	202-B213	Removal of Sign	19.000	EA	20.50	20.00	30.00
0050	202-B215	Removal of Sign Including Post & Footing	107.000	EA	30.50	30.00	110.00
0060	203-G001	Excess Excavation, FM, AH	769.000	CY	6.45	1.00	20.00
0070	304-B004	Granular Material, Class 5, Group D	5,700.000	TON	47.85	56.00	47.00
0080	406-A002	Cold Milling of Bituminous Pavement, All Depths	5,800.000	SY	6.75	9.00	8.00
0090	407-A001	Asphalt for Tack Coat	19,000.000	GAL	4.00	4.48	4.00
0100	423-A001	Rumble Strips, Ground In	25.000	MI	875.00	337.74	280.00
0110	503-C010	Saw Cut, Full Depth	9,231.000	LF	0.01	0.01	5.00
0120	606-B002	Guard Rail, Class A, Type 1, 'W' Beam	550.000	LF	34.75	33.50	33.50
0130	606-D009	Guard Rail, Bridge End Section, Type C	2.000	EA	3,475.00	2,400.00	2,400.00
0140	606-D010	Guard Rail, Bridge End Section, Type C Modified	2.000	EA	3,475.00	2,800.00	2,800.00
0150	606-E005	Guard Rail, Terminal End Section, Flared	4.000	EA	3,600.00	3,750.00	3,750.00
0160	618-B001	Additional Construction Signs	1.000	SF	10.00	10.00	10.00
0170	619-A1001	Temporary Traffic Stripe, Continuous White	49.000	MI	1,730.00	1,700.00	1,700.00
0180	619-A2001	Temporary Traffic Stripe, Continuous Yellow	38.000	MI	1,830.00	1,800.00	1,800.00
0190	619-A4002	Temporary Traffic Stripe, Skip Yellow	9.000	MI	1,830.00	1,800.00	1,800.00
0200	619-A5001	Temporary Traffic Stripe, Detail	5,262.000	LF	1.05	1.00	1.00
0210	619-A6002	Temporary Traffic Stripe, Legend	2,188.000	LF	2.05	2.00	2.00
0220	620-A001	Mobilization	1.000	LS	590,000.00	545,090.04	1,924,704.34
0230	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	71.000	SF	20.50	20.00	21.00
0240	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	746.000	SF	22.50	22.00	24.00
0250	630-A005	Standard Roadside Signs, Sheet Aluminum, 0.1" Thickness	35.000	SF	21.50	21.00	22.00
0260	630-C005	Square Tube Posts, 2.0 lb/ft	1,770.000	LF	18.30	18.00	16.00

Mill & Overlay approximately 12.4 miles of SR 9 from SR 9W to the Pontotoc County Line, known as Federal Aid Project No. STP-0050-01(043) / 109755301 in Calhoun County.					Lehman-Roberts Company	APAC - Mississippi, Inc.	Cook & Son, LLC
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$6,949,232.45					\$7,568,195.94	IRREGULAR \$8,224,912.20	\$9,719,846.41
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0270	630-F006	Delineators, Guard Rail, White	26.000	EA	42.15	70.00	26.00
0280	630-G004	Type 3 Object Markers, OM-3R or OM-3L	36.000	EA	105.00	75.00	75.00
0290	907-403-A006	19-mm, ST, Asphalt Pavement	6,025.000	TON	140.05	183.50	197.77
0300	907-403-A015	9.5-mm, ST, Asphalt Pavement	16,300.000	TON	130.00	152.54	147.30
0310	907-403-B012	9.5-mm, ST, Asphalt Pavement, Leveling	2,050.000	TON	127.50	193.39	160.33
0320	907-413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	60.000	LF	11.00	10.00	10.00
0330	907-414-A001	Scrub Seal	188,000.000	SY	3.00	3.15	2.95
0340	907-618-A001	Maintenance of Traffic	1.000	LS	500,000.00	515,856.85	211,000.00
0350	907-619-B001	Temporary Portable Rumble Strips	66.000	LF	280.00	220.00	250.00
0360	907-626-C014	6" Thermoplastic Edge Stripe, Continuous White	25.000	MI	7,550.00	7,400.00	7,400.00
0370	907-626-D005	6" Thermoplastic Traffic Stripe, Skip Yellow	5.000	MI	3,560.00	3,500.00	3,500.00
0380	907-626-E005	6" Thermoplastic Traffic Stripe, Continuous Yellow	19.000	MI	7,550.00	7,400.00	7,400.00
0390	907-626-G004	Thermoplastic Detail Stripe, White	3,322.000	LF	3.05	3.00	3.00
0400	907-626-G005	Thermoplastic Detail Stripe, Yellow	1,940.000	LF	3.05	3.00	3.00
0410	907-626-H010	Thermoplastic Legend, White	2,188.000	LF	4.06	4.00	4.00
0420	907-627-J001	Two-Way Clear Reflective High Performance Raised Markers	640.000	EA	9.25	9.00	9.00
0430	907-627-L001	Two-Way Yellow Reflective High Performance Raised Markers	1,626.000	EA	8.25	8.00	8.00
0440	304-F001	3/4" and Down Crushed Stone Base	1,475.000	TON		35.00	60.00
0450	304-F002	Size 610 Crushed Stone Base	1,475.000	TON	80.20		
0460	304-F003	Size 825B Crushed Stone Base	1,475.000	TON			

Mill & Overlay approximately 12.4 miles of SR 9 from SR 9W to the Pontotoc County Line, known as Federal Aid Project No. STP-0050-01(043) / 109755301 in Calhoun County.					WG Construction Company, Inc.	Falcon Contracting Company, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$6,949,232.45					\$10,811,245.81	\$10,990,578.65	
Ref#	Item	Item Description	Item Qty	Units	4	5	
0010	201-D001	Random Clearing	962.000	STA	3,325.00	3,553.00	
0020	202-B007	Removal of Asphalt Pavement, All Depths	9,226.000	SY	35.00	35.00	
0030	202-B158	Removal of Guard Rail, Including Rails, Posts and Terminal Ends	747.000	LF	8.00	8.00	
0040	202-B213	Removal of Sign	19.000	EA	20.00	31.35	
0050	202-B215	Removal of Sign Including Post & Footing	107.000	EA	30.00	114.95	
0060	203-G001	Excess Excavation, FM, AH	769.000	CY	1.00	1.00	
0070	304-B004	Granular Material, Class 5, Group D	5,700.000	TON	56.00	47.00	
0080	406-A002	Cold Milling of Bituminous Pavement, All Depths	5,800.000	SY	9.00	7.50	
0090	407-A001	Asphalt for Tack Coat	19,000.000	GAL	4.00	4.00	
0100	423-A001	Rumble Strips, Ground In	25.000	MI	450.00	280.00	
0110	503-C010	Saw Cut, Full Depth	9,231.000	LF	0.01	0.01	
0120	606-B002	Guard Rail, Class A, Type 1, 'W' Beam	550.000	LF	33.50	33.50	
0130	606-D009	Guard Rail, Bridge End Section, Type C	2.000	EA	2,400.00	2,400.00	
0140	606-D010	Guard Rail, Bridge End Section, Type C Modified	2.000	EA	2,800.00	2,800.00	
0150	606-E005	Guard Rail, Terminal End Section, Flared	4.000	EA	3,750.00	3,750.00	
0160	618-B001	Additional Construction Signs	1.000	SF	10.00	10.00	
0170	619-A1001	Temporary Traffic Stripe, Continuous White	49.000	MI	1,700.00	1,700.00	
0180	619-A2001	Temporary Traffic Stripe, Continuous Yellow	38.000	MI	1,800.00	1,800.00	
0190	619-A4002	Temporary Traffic Stripe, Skip Yellow	9.000	MI	1,800.00	1,800.00	
0200	619-A5001	Temporary Traffic Stripe, Detail	5,262.000	LF	1.00	1.00	
0210	619-A6002	Temporary Traffic Stripe, Legend	2,188.000	LF	2.00	2.00	
0220	620-A001	Mobilization	1.000	LS	850,000.00	1,295,000.00	
0230	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	71.000	SF	20.00	21.95	
0240	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	746.000	SF	22.00	25.08	
0250	630-A005	Standard Roadside Signs, Sheet Aluminum, 0.1" Thickness	35.000	SF	21.00	22.99	
0260	630-C005	Square Tube Posts, 2.0 lb/ft	1,770.000	LF	18.00	16.72	

Mill & Overlay approximately 12.4 miles of SR 9 from SR 9W to the Pontotoc County Line, known as Federal Aid Project No. STP-0050-01(043) / 109755301 in Calhoun County.					WG Construction Company, Inc.	Falcon Contracting Company, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$6,949,232.45					\$10,811,245.81	\$10,990,578.65	
Ref#	Item	Item Description	Item Qty	Units	4	5	
0270	630-F006	Delineators, Guard Rail, White	26.000	EA	20.00	26.00	
0280	630-G004	Type 3 Object Markers, OM-3R or OM-3L	36.000	EA	100.00	78.38	
0290	907-403-A006	19-mm, ST, Asphalt Pavement	6,025.000	TON	170.00	168.00	
0300	907-403-A015	9.5-mm, ST, Asphalt Pavement	16,300.000	TON	154.00	150.00	
0310	907-403-B012	9.5-mm, ST, Asphalt Pavement, Leveling	2,050.000	TON	175.00	165.00	
0320	907-413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	60.000	LF	100.00	10.00	
0330	907-414-A001	Scrub Seal	188,000.000	SY	3.15	2.80	
0340	907-618-A001	Maintenance of Traffic	1.000	LS	750,000.00	500,000.00	
0350	907-619-B001	Temporary Portable Rumble Strips	66.000	LF	220.00	57.48	
0360	907-626-C014	6" Thermoplastic Edge Stripe, Continuous White	25.000	MI	7,400.00	7,400.00	
0370	907-626-D005	6" Thermoplastic Traffic Stripe, Skip Yellow	5.000	MI	3,500.00	3,500.00	
0380	907-626-E005	6" Thermoplastic Traffic Stripe, Continuous Yellow	19.000	MI	7,400.00	7,400.00	
0390	907-626-G004	Thermoplastic Detail Stripe, White	3,322.000	LF	3.00	3.00	
0400	907-626-G005	Thermoplastic Detail Stripe, Yellow	1,940.000	LF	3.00	3.00	
0410	907-626-H010	Thermoplastic Legend, White	2,188.000	LF	4.00	4.00	
0420	907-627-J001	Two-Way Clear Reflective High Performance Raised Markers	640.000	EA	9.00	9.00	
0430	907-627-L001	Two-Way Yellow Reflective High Performance Raised Markers	1,626.000	EA	8.00	8.00	
0440	304-F001	3/4" and Down Crushed Stone Base	1,475.000	TON			
0450	304-F002	Size 610 Crushed Stone Base	1,475.000	TON			
0460	304-F003	Size 825B Crushed Stone Base	1,475.000	TON	35.50	35.50	