

**Call 05 Mill & Overlay approximately 9.8 miles of SR 25 from Renfro to the Attala County Line, known as Federal Aid Project No. NH-0056-01(106) / 108246301 in Leake County.**

- Q1. Scope of work states repair failed areas by removing full depth asphalt (7" to 9") based on the table on page 121 there is not enough asphalt to remove and replace. Please clarify. The scope of work states mill and overlay 9.8 miles of mainline. Not enough quantity to mill the entire Mainline. Is MDOT's intent based on the typical sections on pages 115, 116, and 127-129 to only mill and overlay bridge ends local roads, the face of the guardrail, EOP and BOP? Scope and typical shows Scrub Seal. Is this by mistake. Scope of work, and SDGRPI conflict typical on page 30. Please clarify.
- A1. See Addendum 1.
- Q2. Notice to Bidder 7632 Typical Section (Page 115) shows fog sealing over all failed areas and scrub seal over the existing roadway. No pay item for fog seal or scrub seal is included.
- A2. See Addendum 1.
- Q3. In the Special Provision 907-401-3 of the proposal, Section 907-401.03.1.2 Tack Coat section does not discuss the other options on tack coats that are not on the approved product list like the Special Provision normally does. Those products are CSS-1, CSS-1H, SS-1, and SS1-h. Will those products be allowed for this project?
- A3. No.
- Q4. **1.)** If milling on the mainline is limited to tie ins only, does MDOT still intend to enforce the 5 day cover requirement for mainline milled areas as stated on page 107 of the contract documents? **2.)** Do the fog seal (note #6) and scrub seal (note #7) items shown on the typical section on page 115 apply to this project, and if so, will corresponding pay items be added?
- A4. **1.)** See Addendum 1. **2.)** See Addendum 1.
- Q5. **1.)** The chart on sheet 118 is for excess excavation but doesn't state what it is for. Is this to be associated with another scope of work? **2.)** In the scope of work there is mention of "all underdrain outlets shall be cleaned and free of debris", please explain the intent of this. Does this mean cleanout of the entire outfall pipe or just around the outlet opening/concrete pad? Can a pay item be set up for this to establish how many there are?
- A5. **1.)** The excess pay item is to be used when performing the failed area repair at Station 156+72. **2.)** The cleaning of the underdrains pertains to the outlet pipe opening and the concrete apron. This work shall be absorbed.