

Restricted Crossing U-Turn (RCUT) on US 84 at MS 33, known as Federal Aid Project No. HSIP-0015-01(151) / 109580301 in Franklin County.					Midway Construction, Inc.	Simmons Erosion Control, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,009,842.75					\$3,750,809.47	\$4,325,344.80	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0010	201-B001	Clearing and Grubbing	4.000	ACRE	500.00	8,987.75	
0020	202-B007	Removal of Asphalt Pavement, All Depths	1,150.000	SY	10.00	17.65	
0030	202-B052	Removal of Concrete Driveways, All Depths	289.000	SY	10.00	17.65	
0040	202-B063	Removal of Concrete Paved Ditch	119.000	SY	10.00	17.65	
0050	202-B088	Removal of Curb & Gutter, All Types	1,769.000	LF	8.00	17.65	
0060	202-B168	Removal of Island Pavement, All Types	1,367.000	SY	8.00	17.65	
0070	202-B191	Removal of Pipe, 8" And Above	182.000	LF	8.00	17.65	
0080	203-A001	Unclassified Excavation, FM, AH	9,485.000	CY	12.00	18.25	
0090	203-EX020	Borrow Excavation, AH, FME, Class B9	6,441.000	CY	18.00	31.25	
0100	203-G002	Excess Excavation, LVM, AH	2,018.000	CY	10.00	14.50	
0110	206-A001	Structure Excavation	173.000	CY	1.00	55.00	
0120	209-A005	Geotextile Stabilization, Type V, Non-Woven	29,289.000	SY	3.00	3.25	
0130	211-B001	Topsoil for Slope Treatment, Contractor Furnished	1,880.000	CY	1.00	0.01	
0140	213-C001	Superphosphate	4.000	TON	200.00	1,000.00	
0150	216-A001	Solid Sodding	703.000	SY	12.00	6.50	
0160	219-A001	Watering	14.000	KGAL	20.00	20.00	
0170	220-A001	Insect Pest Control	4.000	ACRE	30.00	30.00	
0180	221-A001	Concrete Paved Ditch	33.000	CY	850.00	1,127.50	
0190	223-A001	Mowing	14.000	ACRE	70.00	70.00	
0200	225-A001	Grassing	7.000	ACRE	3,000.00	1,000.00	
0210	225-B001	Agricultural Limestone	4.000	TON	200.00	100.00	
0220	225-C001	Mulch, Vegetative Mulch	14.000	TON	500.00	200.00	
0230	226-A001	Temporary Grassing	7.000	ACRE	500.00	850.00	
0240	237-A002	Wattles, 20"	680.000	LF	10.00	6.50	
0250	249-A001	Riprap for Erosion Control	78.000	TON	150.00	150.00	
0260	249-B001	Remove and Reset Riprap	36.000	CY	10.00	125.00	

Restricted Crossing U-Turn (RCUT) on US 84 at MS 33, known as Federal Aid Project No. HSIP-0015-01(151) / 109580301 in Franklin County.					Midway Construction, Inc.	Simmons Erosion Control, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,009,842.75					\$3,750,809.47	\$4,325,344.80	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0270	304-A008	Granular Material, LVM, Class 6, Group D	2,793.000	CY	33.00	37.75	
0280	406-D001	Fine Milling of Bituminous Pavement, All Depths	3,872.000	SY	5.50	14.00	
0290	503-C010	Saw Cut, Full Depth	6,761.000	LF	2.00	7.75	
0300	602-A001	Reinforcing Steel	217.000	LBS	5.00	2.50	
0310	603-ALT003	18" Type A Alternate Pipe	336.000	LF	75.00	71.00	
0320	603-CA011	18" Reinforced Concrete Pipe, Class III	64.000	LF	75.00	90.50	
0330	603-CA026	24" Reinforced Concrete Pipe, Class III	208.000	LF	90.00	117.00	
0340	603-CA055	36" Reinforced Concrete Pipe, Class III	32.000	LF	170.00	196.00	
0350	603-CB003	18" Reinforced Concrete End Section	2.000	EA	1,050.00	1,967.50	
0360	603-CB004	24" Reinforced Concrete End Section	1.000	EA	1,500.00	2,362.00	
0370	603-CB006	36" Reinforced Concrete End Section	2.000	EA	2,500.00	3,113.75	
0380	604-A001	Castings	244.000	LBS	8.00	7.00	
0390	604-B001	Gratings	450.000	LBS	8.00	7.00	
0400	605-AA001	Geotextile for Subsurface Drainage, Type III	151.000	SY	4.00	3.25	
0410	605-O002	4" Perforated Sewer Pipe for Underdrains, SDR 23.5	339.000	LF	15.00	20.00	
0420	605-W001	Filter Material for Combination Storm Drain and/or Underdrains, Type A, FM	12.000	CY	125.00	300.00	
0430	606-B002	Guard Rail, Class A, Type 1, 'W' Beam	500.000	LF	31.50	39.00	
0440	606-C003	Guard Rail, Cable Anchor, Type 1	2.000	EA	1,450.00	1,800.00	
0450	606-E007	Guard Rail, Terminal End Section, Non-Flared	2.000	EA	3,800.00	4,725.00	
0460	609-B003	Concrete Curb, Special Design	32.000	LF	95.00	87.50	
0470	609-D004	Combination Concrete Curb and Gutter Type 2 Modified	3,676.000	LF	26.00	43.00	
0480	609-D012	Combination Concrete Curb and Gutter Type 3A Modified	617.000	LF	28.00	43.00	
0490	616-A001	Concrete Median and/or Island Pavement, 10-inch	198.000	SY	131.00	170.00	
0500	616-A004	Concrete Median and/or Island Pavement, 4-inch	3,416.000	SY	65.00	55.75	
0510	619-A1002	Temporary Traffic Stripe, Continuous White	3,308.000	LF	1.50	1.75	
0520	619-A2002	Temporary Traffic Stripe, Continuous Yellow	1,977.000	LF	1.50	1.75	

Restricted Crossing U-Turn (RCUT) on US 84 at MS 33, known as Federal Aid Project No. HSIP-0015-01(151) / 109580301 in Franklin County.					Midway Construction, Inc.	Simmons Erosion Control, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,009,842.75					\$3,750,809.47	\$4,325,344.80	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0530	619-A5001	Temporary Traffic Stripe, Detail	15,362.000	LF	0.50	0.60	
0540	619-A6001	Temporary Traffic Stripe, Legend	321.000	SF	1.00	1.20	
0550	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	91.000	SF	11.66	10.00	
0560	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	1,879.000	SF	11.66	10.00	
0570	619-E1001	Flashing Arrow Panel, Type C	2.000	EA	5,830.00	2,500.00	
0580	619-G4001	Barricades, Type III, Double Faced	24.000	LF	24.38	28.75	
0590	619-G4005	Barricades, Type III, Single Faced	528.000	LF	37.10	25.00	
0600	619-G5001	Free Standing Plastic Drums	159.000	EA	68.90	56.00	
0610	619-G7001	Warning Lights, Type "B"	26.000	EA	265.00	168.00	
0620	620-A001	Mobilization	1.000	LS	250,000.00	245,182.50	
0630	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	244.000	SF	21.00	27.00	
0640	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	73.000	SF	22.00	28.50	
0650	630-A005	Standard Roadside Signs, Sheet Aluminum, 0.1" Thickness	191.000	SF	23.00	29.75	
0660	630-C001	Square Tube Posts, 4.0 lb/ft	966.000	LF	45.00	58.00	
0670	630-C005	Square Tube Posts, 2.0 lb/ft	75.000	LF	15.00	19.25	
0680	630-F006	Delineators, Guard Rail, White	18.000	EA	26.00	33.00	
0690	699-A001	Roadway Construction Stakes	1.000	LS	10,000.00	16,128.75	
0700	815-A007	Loose Riprap, Size 300	374.000	TON	100.00	106.50	
0710	815-E001	Geotextile under Riprap	461.000	SY	4.00	3.25	
0720	815-F002	Sediment Control Stone	44.000	TON	175.00	150.00	
0730	907-234-A001	Temporary Silt Fence	2,175.000	LF	10.00	4.00	
0740	907-403-A002	12.5-mm, MT, Asphalt Pavement	1,186.000	TON	148.00	177.50	
0750	907-403-A005	19-mm, MT, Asphalt Pavement	1,479.000	TON	145.00	173.75	
0760	907-403-A006	19-mm, ST, Asphalt Pavement	1,479.000	TON	136.00	163.00	
0770	907-403-A014	9.5-mm, MT, Asphalt Pavement	1,598.000	TON	170.00	204.00	
0780	907-407-A001	Asphalt for Tack Coat	2,660.000	GAL	3.75	4.50	

Restricted Crossing U-Turn (RCUT) on US 84 at MS 33, known as Federal Aid Project No. HSIP-0015-01(151) / 109580301 in Franklin County.					Midway Construction, Inc.	Simmons Erosion Control, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,009,842.75					\$3,750,809.47	\$4,325,344.80	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0790	907-601-B001	Class "B" Structural Concrete, Minor Structures	14.000	CY	2,000.00	2,640.00	
0800	907-618-A001	Maintenance of Traffic	1.000	LS	22,949.00	124,975.00	
0810	907-626-B005	6" Thermoplastic Traffic Stripe, Continuous White	3,049.000	LF	1.75	2.00	
0820	907-626-E006	6" Thermoplastic Traffic Stripe, Continuous Yellow	3,058.000	LF	1.75	2.00	
0830	907-626-G004	Thermoplastic Detail Stripe, White	12,346.000	LF	4.50	5.35	
0840	907-626-G005	Thermoplastic Detail Stripe, Yellow	7,111.000	LF	4.50	5.35	
0850	907-626-H009	Thermoplastic Legend, White	1,043.000	SF	10.00	12.00	
0860	907-627-J001	Two-Way Clear Reflective High Performance Raised Markers	128.000	EA	12.00	14.25	
0870	907-627-K001	Red-Clear Reflective High Performance Raised Markers	310.000	EA	12.00	14.25	
0880	907-627-L001	Two-Way Yellow Reflective High Performance Raised Markers	251.000	EA	12.00	14.25	
0890	907-630-PP002	Roadside Directional Signs, Sheet Aluminum, 0.125" Thickness, Ground Mounted Roadside Directional Signs, Sheet Aluminum, 0.125" Thickness, Ground Mounted	170.000	SF	29.00	36.00	
0900	304-F001	3/4" and Down Crushed Stone Base	12,519.000	TON			
0910	304-F002	Size 610 Crushed Stone Base	12,519.000	TON	93.00	84.00	
0920	304-F003	Size 825B Crushed Stone Base	12,519.000	TON			