

Call 02 Emergency Slope Repair & Pipe Cleanout on SR 26, known as Federal Aid Project Nos. ER-0028-01(056) / 110221301, SP-0028-01(056) / 110221302, ER-0028-01(056) / 110221303 & SP-0028-01(056) / 110221304 in George & Perry Counties.

- Q1. 1.) Will any side roads or driveways be required to be paved? If so, how far back? 2.) It appears that there is no paving on SR 26, just on the detour roads, is that correct?
- A1. 1.) No, the asphalt will be feathered in at driveways and local roads. 2.) Correct.
- Q2. Can a milling qty be added for tie ins to box bridges and bop eops?
- A2. See Addendum 1.
- Q3. Min Lift thickness on 9.5MM is 1" Proposal says to install 3/4" lift
- A3. The 9.5-mm is a leveling lift and will be ¾" and variable thickness.
- Q4. Is in understood that Deep Creek Rd in Stone County will be overlaid from Bendale Rd to SR 26?
- A4. No work is being done in Stone County. Deep Creek Road in George County is where the overlay will occur.