

Add 2 Lanes to I-55 from SR 463 to Gluckstadt Road, & Mill & Overlay approximately 0.77 miles on I-55 from Gluckstadt Road north, known as Federal Aid Project Nos. STP-0055-02(271) / 108168301 & STP-0055-02(275) / 108168302 in Madison County.					Necaise Brothers Construction Co., Inc.	W. G. Yates & Sons Construction Company	Hemphill Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$132,117,148.65					\$195,952,648.70	\$208,867,889.53	\$284,032,160.00
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
0010	201-B001	Clearing and Grubbing	30.000	ACRE	15,000.00	47,500.00	350,000.00
0020	201-D001	Random Clearing	16.000	STA	15,000.00	5,000.00	100,000.00
0030	202-B007	Removal of Asphalt Pavement, All Depths	2,580.000	SY	14.22	15.00	50.00
0040	202-B017	Removal of Box Bridge	4.000	EA	107,197.46	100,000.00	250,000.00
0050	202-B019	Removal of Box Culvert	39.000	LF	766.78	550.00	671.00
0060	202-B059	Removal of Concrete Median & Island Pavement, All Depths	471.000	SY	35.56	30.00	42.50
0070	202-B060	Removal of Concrete Median Barrier	40.000	LF	150.00	300.00	139.50
0080	202-B061	Removal of Concrete Median Barrier, Precast	11,500.000	LF	25.00	10.00	35.50
0090	202-B063	Removal of Concrete Paved Ditch	121.000	SY	59.27	20.00	60.00
0100	202-B069	Removal of Concrete Pavement w/ Variable Depth Overlay	34,294.000	SY	47.41	25.00	50.00
0110	202-B089	Removal of Curb &/or Curb and Gutter, All Types	721.000	LF	24.01	22.00	13.00
0120	202-B096	Removal of Debris and Sand From Box Culvert, 10-foot and Greater Width	802.000	LF	61.34	100.00	127.50
0130	202-B114	Removal of Debris and Sand From Pipe, All Sizes	100.000	LF	61.34	150.00	127.50
0140	202-B126	Removal of Fence, All Types	40,623.000	LF	7.36	5.00	5.00
0150	202-B150	Removal of Guard Rail Including Post, Blockouts & Hardware	4,679.000	LF	6.13	5.25	6.00
0160	202-B160	Removal of High Mast Lighting Assembly	2.000	EA	12,452.70	10,750.00	10,050.00
0170	202-B162	Removal of Impact Attenuator	3.000	EA	1,533.59	1,500.00	1,453.50
0180	202-B165	Removal of Inlets, All Sizes	8.000	EA	1,185.53	1,750.00	1,261.00
0190	202-B177	Removal of Low Mast Lighting Assembly	13.000	EA	1,705.34	1,500.00	1,376.00
0200	202-B191	Removal of Pipe, 8" And Above	538.000	LF	23.71	35.00	50.00
0210	202-B220	Removal of Sign, Overhead Mounted Including Panels, Trust, and Footings	1.000	EA	15,335.84	13,500.00	12,425.00
0220	202-B225	Removal of Soil Cement Shoulders with Asphalt Overlay	55,594.000	SY	15.00	19.00	30.50
0230	202-B226	Removal of Soil Cement Treated Base, All Depths	34,294.000	SY	10.00	6.00	23.50
0240	202-B226	Removal of Soil Cement Treated Base, All Depths - Milling	14,175.000	SY	8.00	13.00	30.50
0250	202-B240	Removal of Traffic Stripe	6,000.000	LF	18.40	16.00	30.00
0260	202-B273	Removal of Debris and Sand From Box Culvert, 6-foot to Less than 10-foot Width	145.000	LF	61.34	150.00	127.50

Add 2 Lanes to I-55 from SR 463 to Gluckstadt Road, & Mill & Overlay approximately 0.77 miles on I-55 from Gluckstadt Road north, known as Federal Aid Project Nos. STP-0055-02(271) / 108168301 & STP-0055-02(275) / 108168302 in Madison County.					Necaise Brothers Construction Co., Inc.	W. G. Yates & Sons Construction Company	Hemphill Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$132,117,148.65					\$195,952,648.70	\$208,867,889.53	\$284,032,160.00
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
0270	202-B276	Removal of Debris from Drainage Channel	690.000	LF	53.34	150.00	127.50
0280	203-EX021	Borrow Excavation, AH, FME, Class B9-6	583,811.000	CY	30.47	36.00	30.00
0290	203-F001	Channel Excavation, FM	15,151.000	CY	30.00	25.00	43.00
0300	203-G001	Excess Excavation, FM, AH	498,248.000	CY	20.00	25.00	25.00
0310	206-A001	Structure Excavation	2,935.000	CY	30.00	65.00	27.00
0320	206-B001	Select Material for Undercuts, Contractor Furnished, FM	96.000	CY	128.92	250.00	210.00
0330	209-A005	Geotextile Stabilization, Type V, Non-Woven	279,624.000	SY	3.00	3.00	6.50
0340	211-B001	Topsoil for Slope Treatment, Contractor Furnished	29,750.000	CY	32.31	5.00	30.00
0350	213-C001	Superphosphate	56.000	TON	1,104.18	915.00	859.50
0360	216-A001	Solid Sodding	2,873.000	SY	9.20	8.00	7.00
0370	217-A001	Ditch Liner	2,209.000	SY	3.07	3.00	5.00
0380	219-A001	Watering	59.000	KGAL	20.00	20.00	20.00
0390	220-A001	Insect Pest Control	56.000	ACRE	30.00	30.00	30.00
0400	221-A001	Concrete Paved Ditch	3,548.000	CY	1,149.13	875.00	778.50
0410	223-A001	Mowing	851.000	ACRE	70.00	70.00	70.00
0420	224-A001	Soil Reinforcing Mat	7,370.000	SY	4.29	4.00	5.00
0430	225-A001	Grassing	111.000	ACRE	1,533.58	1,275.00	1,194.00
0440	225-B001	Agricultural Limestone	56.000	TON	134.96	110.00	105.00
0450	225-C001	Mulch, Vegetative Mulch	222.000	TON	257.64	215.00	200.50
0460	226-A001	Temporary Grassing	111.000	ACRE	1,226.87	1,025.00	955.00
0470	236-A008	Silt Basin, Type D	8.000	EA	12,268.62	7,500.00	11,875.00
0480	237-A002	Wattles, 20"	4,500.000	LF	7.36	6.25	20.00
0490	239-A001	Temporary Slope Drains	2,000.000	LF	15.00	25.00	19.00
0500	245-A001	Silt Dike	2,000.000	LF	18.40	15.50	14.50
0510	246-B002	Rockbags	4,000.000	LF	18.40	15.50	14.50
0520	249-A001	Riprap for Erosion Control	8,000.000	TON	125.76	150.00	120.50

Add 2 Lanes to I-55 from SR 463 to Gluckstadt Road, & Mill & Overlay approximately 0.77 miles on I-55 from Gluckstadt Road north, known as Federal Aid Project Nos. STP-0055-02(271) / 108168301 & STP-0055-02(275) / 108168302 in Madison County.					Necaise Brothers Construction Co., Inc.	W. G. Yates & Sons Construction Company	Hemphill Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$132,117,148.65					\$195,952,648.70	\$208,867,889.53	\$284,032,160.00
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
0530	304-D002	Granular Material, Crushed Stone	18,150.000	TON	101.00	100.00	150.00
0540	307-B003	6" Soil-Lime-Water Mixing, Class B	118,950.000	SY	12.33	7.50	8.00
0550	307-D001	Lime	1,606.000	TON	957.04	900.00	500.00
0560	307-S001	Bituminous Curing Seal	29,738.000	GAL	9.79	4.50	9.50
0570	308-A001	Cement	1,071.000	TON	316.25	150.00	283.00
0580	308-B003	Soil-Cement-Water Mixing, Optional Mixers, Design Soil	118,950.000	SY	1.59	2.00	8.00
0590	308-S001	Bituminous Curing Seal	29,738.000	GAL	9.79	4.50	9.50
0600	406-D001	Fine Milling of Bituminous Pavement, All Depths	302,705.000	SY	5.46	4.25	6.00
0610	423-A001	Rumble Strips, Ground In	17.000	MI	754.52	375.00	338.00
0620	501-K001	Transverse Grooving	222.000	SY	12.27	3.00	3.00
0630	503-C010	Saw Cut, Full Depth	40,670.000	LF	20.00	9.00	7.50
0640	602-A001	Reinforcing Steel	48,821.000	LBS	4.00	3.00	3.50
0650	603-ALT003	18" Type A Alternate Pipe	72.000	LF	129.61	130.00	80.00
0660	603-CA011	18" Reinforced Concrete Pipe, Class III	1,032.000	LF	179.39	125.00	80.00
0670	603-CA022	18" Reinforced Concrete Pipe, Class V, Jacked or Bored	2,024.000	LF	1,345.75	1,100.00	1,178.50
0680	603-CA026	24" Reinforced Concrete Pipe, Class III	824.000	LF	145.57	150.00	102.00
0690	603-CA038	24" Reinforced Concrete Pipe, Class V, Jacked or Bored	632.000	LF	1,491.91	1,200.00	1,410.50
0700	603-CA040	30" Reinforced Concrete Pipe, Class III	8.000	LF	169.96	300.00	184.00
0710	603-CA055	36" Reinforced Concrete Pipe, Class III	96.000	LF	375.46	300.00	184.00
0720	603-CA065	36" Reinforced Concrete Pipe, Class V, Jacked or Bored	224.000	LF	1,636.69	1,400.00	1,670.00
0730	603-CA066	42" Reinforced Concrete Pipe, Class III	16.000	LF	256.67	350.00	183.00
0740	603-CB003	18" Reinforced Concrete End Section	28.000	EA	2,599.83	1,500.00	1,490.00
0750	603-CB004	24" Reinforced Concrete End Section	20.000	EA	2,759.33	1,900.00	1,690.50
0760	603-CB005	30" Reinforced Concrete End Section	1.000	EA	2,958.11	2,300.00	1,894.50
0770	603-CB006	36" Reinforced Concrete End Section	4.000	EA	3,237.80	3,100.00	3,331.50
0780	603-CB007	42" Reinforced Concrete End Section	2.000	EA	8,748.12	4,200.00	2,951.50

Add 2 Lanes to I-55 from SR 463 to Gluckstadt Road, & Mill & Overlay approximately 0.77 miles on I-55 from Gluckstadt Road north, known as Federal Aid Project Nos. STP-0055-02(271) / 108168301 & STP-0055-02(275) / 108168302 in Madison County.					Necaise Brothers Construction Co., Inc.	W. G. Yates & Sons Construction Company	Hemphill Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$132,117,148.65					\$195,952,648.70	\$208,867,889.53	\$284,032,160.00
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
0790	603-CE008	29" x 18" Concrete Arch Pipe, Class A III	104.000	LF	156.60	160.00	96.50
0800	603-CE018	44" x 27" Concrete Arch Pipe, Class A III	88.000	LF	333.04	225.00	162.50
0810	603-CE034	65" x 40" Concrete Arch Pipe, Class A III	40.000	LF	487.65	450.00	289.50
0820	603-CF003	29" x 18" Concrete Arch Pipe End Section	2.000	EA	2,012.54	2,000.00	1,749.00
0830	603-CF005	44" x 27" Concrete Arch Pipe End Section	2.000	EA	3,237.81	3,200.00	2,717.00
0840	603-CF008	65" x 40" Concrete Arch Pipe End Section	2.000	EA	9,974.98	5,300.00	4,435.50
0850	603-SB012	18" Branch Connections, Stub into Box Culvert	4.000	EA	9,654.86	5,000.00	2,985.50
0860	603-SB028	24" Branch Connections, Stub into Box Culvert	2.000	EA	10,881.73	10,000.00	2,985.50
0870	604-A001	Castings	79.000	LBS	7.36	15.00	6.00
0880	604-B001	Gratings	10,897.000	LBS	7.36	10.00	6.00
0890	605-AA001	Geotextile for Subsurface Drainage, Type III	424.000	SY	6.57	6.00	3.00
0900	605-O002	4" Perforated Sewer Pipe for Underdrains, SDR 23.5	762.000	LF	29.63	50.00	25.00
0910	605-P002	4" Non-perforated Sewer Pipe for Underdrains, SDR 23.5	190.000	LF	29.64	50.00	25.00
0920	605-W001	Filter Material for Combination Storm Drain and/or Underdrains, Type A, FM	29.000	CY	47.38	250.00	97.50
0930	606-B001	Guard Rail, Class A, Type 1	550.000	LF	34.35	30.00	28.00
0940	606-B006	Guard Rail, Class A, Type 1, Double Faced	313.000	LF	58.89	51.00	47.50
0950	606-C003	Guard Rail, Cable Anchor, Type 1	1.000	EA	2,392.40	2,050.00	1,938.50
0960	606-D022	Guard Rail, Bridge End Section, Type I	4.000	EA	4,600.75	3,950.00	3,727.50
0970	606-E001	Guard Rail, Terminal End Section	5.000	EA	4,723.44	4,050.00	3,827.00
0980	607-B018	60" Type I Chain Link Fence, Class II	40,947.000	LF	18.40	12.75	13.50
0990	607-E001	Barbed Wire Fence, Single Strand	600.000	LF	3.68	0.70	18.00
1000	607-G127	Gate, 3' x 60" Chain Link	12.000	EA	2,821.79	825.00	500.00
1010	607-P1003	Line Post, 14' x 2 1/2" Galvanized Steel	8.000	EA	294.45	150.00	295.00
1020	607-P1008	Line Post, 7' x 1 1/2" Galvanized Steel	3,834.000	EA	147.22	75.00	90.00
1030	607-P2004	Brace Post, 7 1/2' x 2" Galvanized Steel	247.000	EA	159.49	280.00	400.00
1040	607-P2022	Brace Post, 5' x 2 1/2" Galvanized Steel	8.000	EA	134.96	280.00	370.00

Add 2 Lanes to I-55 from SR 463 to Gluckstadt Road, & Mill & Overlay approximately 0.77 miles on I-55 from Gluckstadt Road north, known as Federal Aid Project Nos. STP-0055-02(271) / 108168301 & STP-0055-02(275) / 108168302 in Madison County.					Necaise Brothers Construction Co., Inc.	W. G. Yates & Sons Construction Company	Hemphill Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$132,117,148.65					\$195,952,648.70	\$208,867,889.53	\$284,032,160.00
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
1050	607-P3004	Gate Post, 8' x 2 1/2" Galvanized Steel	24.000	EA	184.03	300.00	340.00
1060	608-A001	Concrete Sidewalk, Without Reinforcement	870.000	SY	90.18	70.00	65.50
1070	609-C001	Concrete Integral Curb, Type 1	173.000	LF	52.76	41.00	38.00
1080	609-D004	Combination Concrete Curb and Gutter Type 2 Modified	1,785.000	LF	53.06	40.00	37.50
1090	609-D007	Combination Concrete Curb and Gutter Type 3 Modified	3,101.000	LF	48.16	36.00	34.00
1100	612-B001	Flowable Fill, Non-Excavatable	22.000	CY	118.49	450.00	500.00
1110	615-A004	Concrete Bridge End Barrier, 43.5"	287.000	LF	217.46	230.00	169.50
1120	615-A007	Concrete Pier Protection Barrier, 54"	256.000	LF	945.30	835.00	736.00
1130	615-A023	Concrete Type IV Modified, 42" Height, Cast-in-Place Median Barrier	34,372.000	LF	340.88	330.00	265.50
1140	616-A001	Concrete Median and/or Island Pavement, 10-inch	155.000	SY	230.35	220.00	160.00
1150	616-A004	Concrete Median and/or Island Pavement, 4-inch	1,127.000	SY	92.64	115.00	58.00
1160	616-B001	Bituminous Median and/or Island Pavement	776.000	SY	132.50	105.00	58.00
1170	617-A001	Right-of-Way Marker	3.000	EA	368.06	1,050.00	1,652.00
1180	619-A1001	Temporary Traffic Stripe, Continuous White	84.000	MI	1,840.30	1,575.00	1,438.50
1190	619-A2001	Temporary Traffic Stripe, Continuous Yellow	81.000	MI	1,840.30	1,575.00	1,438.50
1200	619-A3001	Temporary Traffic Stripe, Skip White	96.000	MI	1,840.30	1,575.00	1,438.50
1210	619-A5001	Temporary Traffic Stripe, Detail	142,991.000	LF	0.37	0.35	0.50
1220	619-A6001	Temporary Traffic Stripe, Legend	3,431.000	SF	1.23	1.05	1.00
1230	619-A6002	Temporary Traffic Stripe, Legend	2,568.000	LF	1.23	1.05	1.00
1240	619-C6001	Red-Clear Reflective High Performance Raised Marker	20,347.000	EA	6.13	5.25	5.00
1250	619-C8001	One-Way Clear Reflective High Performance Raised Marker	2,075.000	EA	18.40	15.75	14.50
1260	619-C9001	One-Way Yellow Reflective High Performance Raised Marker	2,099.000	EA	18.40	15.75	14.50
1270	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	95.000	SF	14.72	12.50	20.00
1280	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	2,060.000	SF	14.72	12.50	20.00
1290	619-F1001	Concrete Median Barrier, Precast	1,000.000	LF	50.00	105.00	125.00
1300	619-F2001	Remove and Reset Concrete Median Barrier, Precast	84,948.000	LF	15.00	20.00	50.00

Add 2 Lanes to I-55 from SR 463 to Gluckstadt Road, & Mill & Overlay approximately 0.77 miles on I-55 from Gluckstadt Road north, known as Federal Aid Project Nos. STP-0055-02(271) / 108168301 & STP-0055-02(275) / 108168302 in Madison County.					Necaise Brothers Construction Co., Inc.	W. G. Yates & Sons Construction Company	Hemphill Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$132,117,148.65					\$195,952,648.70	\$208,867,889.53	\$284,032,160.00
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
1310	619-G4005	Barricades, Type III, Single Faced	228.000	LF	36.81	31.00	35.00
1320	619-G5001	Free Standing Plastic Drums	847.000	EA	73.61	63.00	70.00
1330	619-G7001	Warning Lights, Type "B"	22.000	EA	153.36	130.00	250.00
1340	619-J1004	Impact Attenuator, 60 MPH	4.000	EA	9,201.50	7,800.00	10,000.00
1350	619-J2004	Impact Attenuator, 60 MPH, Replacement Package	4.000	EA	5,520.90	4,700.00	6,000.00
1360	619-J3001	Remove and Reset Impact Attenuator	20.000	EA	3,067.17	2,600.00	3,000.00
1370	620-A001	Mobilization	1.000	LS	21,500,000.00	20,325,000.00	28,475,000.00
1380	622-A004	Engineer's Field Office Building, Type 3	1.000	EA	61,343.11	250,000.00	650,000.00
1390	629-A005	Vehicular Impact Attenuator, 70 MPH	1.000	EA	128,820.53	47,500.00	125,000.00
1400	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	178.000	SF	25.76	22.00	21.00
1410	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	469.000	SF	26.99	23.00	22.00
1420	630-A005	Standard Roadside Signs, Sheet Aluminum, 0.1" Thickness	349.000	SF	26.38	23.00	21.50
1430	630-B002	Interstate Directional Signs, Bolted Extruded Aluminum Panels, Ground Mounted	378.000	SF	38.03	33.00	31.00
1440	630-B003	Interstate Directional Signs, Bolted Extruded Aluminum Panels, Overhead Mounted	7,776.000	SF	39.26	34.00	32.00
1450	630-C001	Square Tube Posts, 4.0 lb/ft	559.000	LF	63.80	55.00	51.50
1460	630-C004	Square Tube Posts, 9.0 lb/ft	136.000	LF	104.28	90.00	84.50
1470	630-C005	Square Tube Posts, 2.0 lb/ft	944.000	LF	23.31	20.00	19.00
1480	630-C1001	Square Post Inner Sleeve	64.000	LF	23.31	20.00	19.00
1490	630-D006	Structural Steel Beams, W6 x 12	51.000	LF	104.28	90.00	84.50
1500	630-D008	Structural Steel Beams, W6 x 9	136.000	LF	104.28	90.00	84.50
1510	630-E001	Structural Steel Angles & Bars, 3 1/2" x 3 1/2" x 1/4" Angles	63.000	LBS	6.13	5.25	5.00
1520	630-E002	Structural Steel Angles & Bars, 3" x 3" x 1/4" Angles	132.000	LBS	6.13	5.25	5.00
1530	630-F006	Delineators, Guard Rail, White	28.000	EA	36.81	31.50	30.00
1540	630-F007	Delineators, Guard Rail, Yellow	10.000	EA	36.81	31.50	30.00
1550	630-F010	Delineators, Post Mounted, Double White	152.000	EA	122.69	105.00	99.50
1560	630-F011	Delineators, Post Mounted, Double Yellow	54.000	EA	122.69	105.00	99.50

Add 2 Lanes to I-55 from SR 463 to Gluckstadt Road, & Mill & Overlay approximately 0.77 miles on I-55 from Gluckstadt Road north, known as Federal Aid Project Nos. STP-0055-02(271) / 108168301 & STP-0055-02(275) / 108168302 in Madison County.					Necaise Brothers Construction Co., Inc.	W. G. Yates & Sons Construction Company	Hemphill Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$132,117,148.65					\$195,952,648.70	\$208,867,889.53	\$284,032,160.00
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
1570	630-F012	Delineators, Post Mounted, Single White	61.000	EA	116.55	100.00	94.50
1580	630-F013	Delineators, Post Mounted, Single Yellow	14.000	EA	116.55	100.00	94.50
1590	630-G004	Type 3 Object Markers, OM-3R or OM-3L	4.000	EA	165.63	145.00	134.00
1600	630-I003	Metal Overhead Sign Supports, Assembly No. 1, Contractor Designed	1.000	LS	251,507.72	300,000.00	203,770.00
1610	630-I004	Metal Overhead Sign Supports, Assembly No. 10, Contractor Designed	1.000	LS	251,507.72	300,000.00	203,770.00
1620	630-I005	Metal Overhead Sign Supports, Assembly No. 11, Contractor Designed	1.000	LS	251,507.72	300,000.00	203,770.00
1630	630-I006	Metal Overhead Sign Supports, Assembly No. 12, Contractor Designed	1.000	LS	251,507.72	300,000.00	203,770.00
1640	630-I007	Metal Overhead Sign Supports, Assembly No. 13, Contractor Designed	1.000	LS	251,507.72	300,000.00	203,770.00
1650	630-I008	Metal Overhead Sign Supports, Assembly No. 14, Contractor Designed	1.000	LS	251,507.72	300,000.00	203,770.00
1660	630-I009	Metal Overhead Sign Supports, Assembly No. 15, Contractor Designed	1.000	LS	251,507.72	300,000.00	203,700.00
1670	630-I010	Metal Overhead Sign Supports, Assembly No. 16, Contractor Designed	1.000	LS	561,684.23	350,000.00	291,037.00
1680	630-I015	Metal Overhead Sign Supports, Assembly No. 2, Contractor Designed	1.000	LS	251,507.72	300,000.00	236,942.00
1690	630-I020	Metal Overhead Sign Supports, Assembly No. 3, Contractor Designed	1.000	LS	251,507.72	300,000.00	203,770.00
1700	630-I022	Metal Overhead Sign Supports, Assembly No. 4, Contractor Designed	1.000	LS	251,507.72	300,000.00	203,770.00
1710	630-I024	Metal Overhead Sign Supports, Assembly No. 5, Contractor Designed	1.000	LS	251,507.72	300,000.00	203,770.00
1720	630-I025	Metal Overhead Sign Supports, Assembly No. 6, Contractor Designed	1.000	LS	251,507.72	300,000.00	203,770.00
1730	630-I026	Metal Overhead Sign Supports, Assembly No. 7, Contractor Designed	1.000	LS	251,507.72	300,000.00	203,770.00
1740	630-I027	Metal Overhead Sign Supports, Assembly No. 8, Contractor Designed	1.000	LS	251,507.72	300,000.00	203,770.00
1750	630-I028	Metal Overhead Sign Supports, Assembly No. 9, Contractor Designed	1.000	LS	251,507.72	300,000.00	203,770.00
1760	635-A059	Traffic Signal Head, Type 1	12.000	EA	1,300.48	1,125.00	1,049.50
1770	635-A065	Traffic Signal Head, Type 2 FYA	2.000	EA	2,607.10	2,250.00	2,104.00
1780	635-A070	Traffic Signal Head, Type 3	2.000	EA	2,607.10	2,250.00	2,104.00
1790	635-A073	Traffic Signal Head, Type 4	1.000	EA	1,300.48	1,125.00	1,049.50
1800	635-A076	Traffic Signal Head, Type 6	2.000	EA	1,300.48	1,125.00	1,049.50
1810	647-A001	Removal of Existing Traffic Signal Equipment	1.000	LS	3,913.71	3,350.00	3,158.00
1820	682-A005	Underground Branch Circuit, AWG 1/0, 3 Conductor	4,378.000	LF	30.30	26.00	24.50

Add 2 Lanes to I-55 from SR 463 to Gluckstadt Road, & Mill & Overlay approximately 0.77 miles on I-55 from Gluckstadt Road north, known as Federal Aid Project Nos. STP-0055-02(271) / 108168301 & STP-0055-02(275) / 108168302 in Madison County.					Necaise Brothers Construction Co., Inc.	W. G. Yates & Sons Construction Company	Hemphill Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$132,117,148.65					\$195,952,648.70	\$208,867,889.53	\$284,032,160.00
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
1830	682-A007	Underground Branch Circuit, AWG 1/0, 5 Conductor	2,642.000	LF	44.66	38.00	36.00
1840	682-A018	Underground Branch Circuit, AWG 2, 3 Conductor	8,904.000	LF	24.17	21.00	19.50
1850	682-A034	Underground Branch Circuit, AWG 6, 3 Conductor	3,180.000	LF	15.64	13.50	12.50
1860	682-A039	Underground Branch Circuit, AWG 8, 3 Conductor	1,680.000	LF	12.82	11.00	10.50
1870	682-B005	Underground Branch Circuit, Jacked or Bored, AWG 1/0, 3 Conductor	90.000	LF	43.25	37.00	35.00
1880	682-B007	Underground Branch Circuit, Jacked or Bored, AWG 1/0, 5 Conductor	90.000	LF	57.54	50.00	46.50
1890	682-B016	Underground Branch Circuit, Jacked or Bored, AWG 2, 3 Conductor	620.000	LF	33.49	29.00	27.00
1900	682-B025	Underground Branch Circuit, Jacked or Bored, AWG 4, 3 Conductor	870.000	LF	31.84	22.00	25.50
1910	682-B032	Underground Branch Circuit, Jacked or Bored, AWG 6, 3 Conductor	490.000	LF	28.52	25.00	23.00
1920	682-B037	Underground Branch Circuit, Jacked or Bored, AWG 8, 3 Conductor	340.000	LF	26.07	23.00	21.00
1930	682-C006	Structure Mounted Branch Circuit, AWG 1/0, 5 Conductor	200.000	LF	99.44	86.00	80.00
1940	682-C009	Structure Mounted Branch Circuit, AWG 10, 3 Conductor	480.000	LF	42.69	37.00	34.50
1950	682-C015	Structure Mounted Branch Circuit, AWG 2, 3 Conductor	150.000	LF	77.84	67.00	63.00
1960	682-D002	Structure Mounted Pull Box	10.000	EA	2,079.54	1,800.00	1,678.00
1970	682-D003	Underground Pull Box	38.000	EA	2,349.45	2,025.00	1,896.00
1980	682-E001	Structure Mounted Junction Box	3.000	EA	1,791.22	1,550.00	1,445.50
1990	682-E003	Underground Junction Box With Concrete Pad	21.000	EA	3,754.21	3,225.00	3,029.50
2000	682-F002	Secondary Power Controllers	3.000	EA	49,761.72	20,550.00	40,154.50
2010	683-A002	Lighting Assembly, High Mast, LED, Type 120-4-A	32.000	EA	60,153.29	50,500.00	48,539.50
2020	683-A124	Lighting Assembly, High Mast, LED, Type 120-8-S	4.000	EA	69,477.48	58,500.00	56,063.50
2030	683-A137	Lighting Assembly, High Mast, LED, Type 120-8-A	1.000	EA	69,741.25	58,750.00	56,276.50
2040	683-A138	Lighting Assembly, High Mast, LED, Type 120-6-A	1.000	EA	64,723.37	54,500.00	52,227.50
2050	683-B212	Lighting Assembly, Low Mast, LED, Type 40-1-8-110	11.000	EA	6,306.10	5,400.00	5,088.50
2060	683-B213	Lighting Assembly, Low Mast, LED, Type 40-2-8-110	1.000	EA	8,508.33	7,300.00	6,865.50
2070	683-C010	Lighting Assembly, Underpass, Type UP	8.000	EA	1,545.85	1,325.00	1,247.50
2080	683-D001	Portable Electric Power Units	1.000	EA	5,208.05	4,500.00	4,202.50

Add 2 Lanes to I-55 from SR 463 to Gluckstadt Road, & Mill & Overlay approximately 0.77 miles on I-55 from Gluckstadt Road north, known as Federal Aid Project Nos. STP-0055-02(271) / 108168301 & STP-0055-02(275) / 108168302 in Madison County.					Necaise Brothers Construction Co., Inc.	W. G. Yates & Sons Construction Company	Hemphill Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$132,117,148.65					\$195,952,648.70	\$208,867,889.53	\$284,032,160.00
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
2090	684-A003	Pole Foundation, 24" Diameter	12.000	CY	2,766.59	2,400.00	2,232.50
2100	684-A006	Pole Foundation, 42" Diameter	271.000	CY	2,803.39	2,200.00	2,262.00
2110	684-B003	Slip Casing, 24" Diameter	8.000	LF	122.69	105.00	99.00
2120	684-B006	Slip Casing, 42" Diameter	20.000	LF	613.43	525.00	495.00
2130	699-A001	Roadway Construction Stakes	1.000	LS	1,226,866.94	3,500,000.00	10,000,000.00
2140	815-A002	Loose Riprap, Size 100	1,250.000	TON	137.82	125.00	120.00
2150	815-A007	Loose Riprap, Size 300	7,050.000	TON	134.87	125.00	150.00
2160	815-E001	Geotextile under Riprap	8,681.000	SY	6.00	5.00	4.50
2170	815-F002	Sediment Control Stone	3,000.000	TON	177.80	150.00	125.00
2180	907-234-A001	Temporary Silt Fence	17,000.000	LF	4.91	6.50	20.00
2190	907-234-C001	Super Silt Fence	2,575.000	LF	18.40	20.00	25.00
2200	907-234-D001	Inlet Siltation Guard	15.000	EA	736.12	625.00	666.50
2210	907-234-E001	Reset Inlet Siltation Guard	15.000	EA	368.06	325.00	333.00
2220	907-248-A001	Temporary Site Drainage	1.000	LS	10,000.00	1,000,000.00	28,911,763.50
2230	907-253-A001	Coir Fiber Baffle	1,021.000	LF	1.00	15.50	16.50
2240	907-402-A002	Open Graded Friction Course, 9.5-mm Mixture	11,193.000	TON	223.90	200.00	210.00
2250	907-402-B001	Bituminous Tack Coat	39,202.000	GAL	5.83	4.50	5.50
2260	907-403-A001	12.5-mm, HT, Asphalt Pavement	29,040.000	TON	172.99	143.00	162.00
2270	907-403-A004	19-mm, HT, Asphalt Pavement	35,680.000	TON	168.08	144.00	157.50
2280	907-403-A006	19-mm, ST, Asphalt Pavement	35,456.000	TON	163.48	137.00	153.00
2290	907-403-A013	9.5-mm, HT, Asphalt Pavement	4,667.000	TON	193.84	170.00	181.50
2300	907-403-A015	9.5-mm, ST, Asphalt Pavement	608.000	TON	225.74	181.00	211.50
2310	907-403-B001	12.5-mm, HT, Asphalt Pavement, Leveling	42,798.000	TON	194.46	155.00	182.50
2320	907-403-B010	9.5-mm, HT, Asphalt Pavement, Leveling	5,921.000	TON	207.95	167.00	195.00
2330	907-403-S001	Joint Sealant	34.000	MI	1,993.65	3,150.00	1,869.00
2340	907-405-A001	Stone Matrix Asphalt, 9.5 mm Mixture	44,502.000	TON	221.14	185.00	207.50

Add 2 Lanes to I-55 from SR 463 to Gluckstadt Road, & Mill & Overlay approximately 0.77 miles on I-55 from Gluckstadt Road north, known as Federal Aid Project Nos. STP-0055-02(271) / 108168301 & STP-0055-02(275) / 108168302 in Madison County.					Necaise Brothers Construction Co., Inc.	W. G. Yates & Sons Construction Company	Hemphill Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$132,117,148.65					\$195,952,648.70	\$208,867,889.53	\$284,032,160.00
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
2350	907-405-A002	Stone Matrix Asphalt, 12.5 mm Mixture	20,101.000	TON	225.74	190.00	211.50
2360	907-407-A001	Asphalt for Tack Coat	116,816.000	GAL	5.83	4.50	5.50
2370	907-413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	576.000	LF	12.27	10.25	11.00
2380	907-501-F001	Concrete Lug Anchors	640.000	LF	789.42	750.00	869.00
2390	907-502-A001	Reinforced Cement Concrete Bridge End Pavement	1,693.000	SY	368.06	325.00	286.50
2400	907-601-A001	Class "B" Structural Concrete	302.000	CY	4,800.00	2,750.00	2,193.00
2410	907-601-B001	Class "B" Structural Concrete, Minor Structures	88.000	CY	4,500.00	7,100.00	4,740.00
2420	907-608-C001	Detectable Warning Panels	120.000	SF	30.67	26.00	24.00
2430	907-618-A001	Maintenance of Traffic	1.000	LS	4,000,000.00	13,350,000.00	35,000,000.00
2440	907-618-M1001	Service Patrol	1.000	LS	650,000.00	5,000,000.00	5,195,851.00
2450	907-618-M2001	Work Zone Law Enforcement	4,640.000	HRS	60.00	60.00	60.00
2460	907-619-E3001	Changeable Message Sign	2.000	EA	12,544.72	10,750.00	10,225.00
2470	907-619-M1002	Smart Work Zone, Portable Queue Trailer	24.000	EA	7,345.87	6,250.00	5,987.50
2480	907-619-M1003	Smart Work Zone, Portable Camera Trailer	10.000	EA	24,518.94	20,775.00	19,985.00
2490	907-619-M1004	Smart Work Zone, Portable Message Board Trailer	12.000	EA	15,313.75	13,000.00	12,482.00
2500	907-619-M2001	Smart Work Zone, Portable Queue Trailer, Operational Month	58.000	EA	444.13	400.00	362.00
2510	907-619-M2002	Smart Work Zone, Portable Camera Trailer, Operational Month	58.000	EA	633.06	550.00	516.00
2520	907-619-M2003	Smart Work Zone, Portable Message Board Trailer, Operational Month	58.000	EA	444.13	400.00	362.00
2530	907-619-M2004	Smart Work Zone, Portable Bluetooth Detection System, Additional Device, Operational Month	58.000	EA	444.13	400.00	362.00
2540	907-619-M3002	Smart Work Zone, System Monitoring, Operational Month	58.000	EA	1,104.18	225.00	900.00
2550	907-626-A010	6" Thermoplastic Traffic Stripe, Skip White	21.000	MI	10,428.37	8,925.00	8,151.50
2560	907-626-B006	6" Thermoplastic Traffic Stripe, Continuous White	14.000	MI	14,967.78	12,800.00	11,700.00
2570	907-626-E005	6" Thermoplastic Traffic Stripe, Continuous Yellow	13.000	MI	14,599.72	12,500.00	11,412.00
2580	907-626-G004	Thermoplastic Detail Stripe, White	37,665.000	LF	4.91	4.20	4.00
2590	907-626-G005	Thermoplastic Detail Stripe, Yellow	1,966.000	LF	4.91	4.20	4.00
2600	907-626-H009	Thermoplastic Legend, White	1,096.000	SF	36.81	31.49	29.00

Add 2 Lanes to I-55 from SR 463 to Gluckstadt Road, & Mill & Overlay approximately 0.77 miles on I-55 from Gluckstadt Road north, known as Federal Aid Project Nos. STP-0055-02(271) / 108168301 & STP-0055-02(275) / 108168302 in Madison County.					Necaise Brothers Construction Co., Inc.	W. G. Yates & Sons Construction Company	Hemphill Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$132,117,148.65					\$195,952,648.70	\$208,867,889.53	\$284,032,160.00
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
2610	907-626-H010	Thermoplastic Legend, White	1,284.000	LF	18.40	15.75	14.50
2620	907-627-K001	Red-Clear Reflective High Performance Raised Markers	4,973.000	EA	18.40	15.75	14.50
2630	907-632-A007	Solid State Traffic Cabinet Assembly, Type III Cabinet, Type 1 Controller	2.000	EA	29,972.36	25,750.00	24,185.50
2640	907-632-D001	Solid State Traffic Actuated Controller, Type 1	2.000	EA	6,514.67	5,575.00	5,257.00
2650	907-632-G001	Malfunction Management Unit	2.000	EA	2,607.10	2,250.00	2,104.00
2660	907-632-J001	Power Service Pedestal	6.000	EA	38,658.58	11,000.00	31,195.00
2670	907-634-A047	Traffic Signal Equipment Pole, Type II(L), 30' Shaft, 55' Arm	1.000	EA	39,087.98	33,500.00	31,541.50
2680	907-634-A083	Traffic Signal Equipment Pole, Type II, 17' Shaft, 45' Arm	1.000	EA	36,487.02	31,250.00	29,442.50
2690	907-634-A374	Traffic Signal Equipment Pole, Type III, 17' Shaft, 35' & 40' Arms	1.000	EA	41,695.08	35,750.00	33,645.00
2700	907-634-A397	Traffic Signal Equipment Pole, Type III, 17' Shaft, 50' & 50' Arms	1.000	EA	52,123.45	44,750.00	42,060.00
2710	907-634-A545	Traffic Signal Equipment Pole, Type VI, 8' Shaft	1.000	EA	1,306.62	1,125.00	1,054.50
2720	907-634-C001	Pole Foundations, Class "B" Concrete	16.000	CY	1,306.61	1,125.00	1,054.50
2730	907-634-E001	Camera Pole with Foundation, 50' Pole	4.000	EA	25,064.89	21,500.00	20,225.50
2740	907-636-B003	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 10, 2 Conductor	190.000	LF	3.93	3.40	3.00
2750	907-636-B014	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 14, 5 Conductor	425.000	LF	3.93	3.40	3.00
2760	907-636-B016	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 14, 8 Conductor	915.000	LF	3.93	3.40	3.00
2770	907-636-B025	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 6, 3 Conductor	225.000	LF	7.85	6.75	6.50
2780	907-636-B043	Electric Cable, Underground in Conduit, THHN, AWG #2, 4 Conductor	40.000	LF	20.37	17.50	16.50
2790	907-636-B053	Electric Cable, Underground in Conduit, THHN, AWG #6, 3 Conductor	1,120.000	LF	5.58	5.00	4.50
2800	907-636-D001	Electric Cable, Aerial Supported in Conduit, IMSA 20-1, AWG 10, 2 Conductor	40.000	LF	3.93	3.40	3.00
2810	907-636-D006	Electric Cable, Aerial Supported in Conduit, IMSA 20-1, AWG 14, 5 Conductor	20.000	LF	3.93	3.40	3.00
2820	907-636-D008	Electric Cable, Aerial Supported in Conduit, IMSA 20-1, AWG 14, 8 Conductor	380.000	LF	3.93	3.40	3.00
2830	907-636-D022	Electric Cable, Aerial Supported in Conduit, IMSA 20-1, AWG 6, 3 Conductor	40.000	LF	7.85	6.75	6.50
2840	907-637-A002	Pullbox Enclosure, Type 2	17.000	EA	1,662.40	1,425.00	1,341.50
2850	907-637-A003	Pullbox Enclosure, Type 3	2.000	EA	2,349.45	2,025.00	1,896.00
2860	907-637-A004	Pullbox Enclosure, Type 4	16.000	EA	2,251.30	1,925.00	1,816.50

Add 2 Lanes to I-55 from SR 463 to Gluckstadt Road, & Mill & Overlay approximately 0.77 miles on I-55 from Gluckstadt Road north, known as Federal Aid Project Nos. STP-0055-02(271) / 108168301 & STP-0055-02(275) / 108168302 in Madison County.					Necaise Brothers Construction Co., Inc.	W. G. Yates & Sons Construction Company	Hemphill Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$132,117,148.65					\$195,952,648.70	\$208,867,889.53	\$284,032,160.00
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
2870	907-637-A005	Pullbox Enclosure, Type 5	11.000	EA	3,036.50	2,600.00	2,450.50
2880	907-637-C028	Traffic Signal Conduit, Underground, Type 4, 2"	160.000	LF	19.57	17.00	16.00
2890	907-637-C030	Traffic Signal Conduit, Underground, Type 4, 3"	105.000	LF	26.07	22.50	21.00
2900	907-637-D003	Traffic Signal Conduit, Underground Drilled or Jacked, Rolled Pipe, 3"	670.000	LF	26.07	22.50	21.00
2910	907-637-H001	Traffic Signal Conduit Bank, Underground, Rolled Pipe, 2 @ 2"	160.000	LF	26.19	22.50	21.00
2920	907-637-H002	Traffic Signal Conduit Bank, Underground, Rolled Pipe, 2"	445.000	LF	19.94	17.00	16.00
2930	907-637-I001	Traffic Signal Conduit Bank, Underground, Drilled or Jacked, Rolled Pipe, 2 @ 2"	23,495.000	LF	13.99	12.00	11.50
2940	907-637-I002	Traffic Signal Conduit Bank, Underground, Drilled or Jacked, Rolled Pipe, 2"	760.000	LF	24.84	21.50	20.00
2950	907-640-B001	Shielded Cable, AWG #14, 2 Conductor	440.000	LF	2.64	2.30	2.00
2960	907-641-A002	Signal Stop Bar Radar Vehicle Detection Sensor, Type 2	6.000	EA	10,428.37	9,000.00	8,415.00
2970	907-641-B002	Signal Advanced Radar Vehicle Detection Sensor, Type 2	8.000	EA	10,428.37	9,000.00	8,415.00
2980	907-641-C002	ITS Radar Vehicle Detection Sensor	2.000	EA	9,968.30	8,500.00	8,044.00
2990	907-641-D001	Radar Vehicle Detection Cable	2,505.000	LF	5.21	4.50	4.00
3000	907-641-F002	Signal Radar Vehicle Detection Processor, Type 2	4.000	EA	7,821.28	6,700.00	6,311.50
3010	907-641-G002	ITS Radar Vehicle Detection Processor, Type 2	2.000	EA	613.44	525.00	495.00
3020	907-645-B001	Accessible Pedestrian Detection Assembly	2.000	EA	1,956.86	1,675.00	1,579.00
3030	907-650-A002	On Street Video Equipment, Fixed Type	12.000	EA	3,748.08	3,225.00	3,024.50
3040	907-650-A003	On Street Video Equipment, PTZ Type	6.000	EA	5,490.23	4,700.00	4,430.50
3050	907-650-A004	On Street Video Equipment, PTZ Type, Signal Monitoring	5.000	EA	3,257.33	2,800.00	2,628.50
3060	907-653-A001	Traffic Sign	27.000	SF	104.28	90.00	84.00
3070	907-656-A001	Dynamic Message Sign, Type 1	1.000	EA	165,314.19	120,500.00	133,397.50
3080	907-659-A001	Traffic Management Center Modifications	1.000	LS	86,954.20	74,500.00	70,166.50
3090	907-660-A002	Equipment Cabinet, Type B	5.000	EA	7,588.17	6,500.00	6,123.00
3100	907-660-A003	Equipment Cabinet, Type C	1.000	EA	16,924.64	14,500.00	13,657.00
3110	907-661-A004	Fiber Optic Cable, 72 SM	20,470.000	LF	3.56	3.04	3.00
3120	907-661-B002	Fiber Optic Drop Cable, 12 SM	3,805.000	LF	4.42	3.80	3.50

Add 2 Lanes to I-55 from SR 463 to Gluckstadt Road, & Mill & Overlay approximately 0.77 miles on I-55 from Gluckstadt Road north, known as Federal Aid Project Nos. STP-0055-02(271) / 108168301 & STP-0055-02(275) / 108168302 in Madison County.					Necaise Brothers Construction Co., Inc.	W. G. Yates & Sons Construction Company	Hemphill Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$132,117,148.65					\$195,952,648.70	\$208,867,889.53	\$284,032,160.00
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
3130	907-663-A001	Network Switch, Type A	10.000	EA	2,110.21	1,825.00	1,703.00
3140	907-663-A002	Network Switch, Type B	1.000	EA	2,809.53	2,425.00	2,267.00
3150	907-663-A003	Network Switch, Type C	1.000	EA	173,086.38	135,000.00	139,669.00
3160	907-663-A005	Network Switch, Type E	2.000	EA	48,516.46	41,750.00	39,149.50
3170	907-666-A001	Bluetooth Detection System, Type A	3.000	EA	9,487.73	8,050.00	15,000.00
3180	907-682-A1011	Branch Circuit Wire, AWG #2, 3 Conductor	440.000	LF	15.52	13.50	12.50
3190	907-682-A1019	Branch Circuit Wire, AWG #4, 3 Conductor	830.000	LF	10.55	9.00	8.50
3192	907-906001	Trainees	1,040.000	HRS	5.00	5.00	5.00
3200	304-F001	3/4" and Down Crushed Stone Base	117,600.000	TON			
3210	304-F002	Size 610 Crushed Stone Base	117,600.000	TON	95.00		
3220	304-F003	Size 825B Crushed Stone Base	117,600.000	TON		110.00	92.50
3230	605-W002	Filter Material for Combination Storm Drain and/or Underdrains, Type B, FM	800.000	CY	150.00	175.00	91.50
3240	605-W003	Filter Material for Combination Storm Drain and/or Underdrains, Type C, FM	800.000	CY			
3250	501-K001	Transverse Grooving	5,588.000	SY	3.37	3.00	2.50
3260	605-AA001	Geotextile for Subsurface Drainage, Type III	2,476.000	SY	40.00	6.00	3.00
3270	605-T002	6" Perforated Pipe for Underdrains	3,262.000	LF	15.00	65.00	30.50
3280	605-X002	Filter Material for Filter Beds, Type A	258.000	CY	170.00	300.00	108.50
3290	605-X003	Filter Material for Filter Beds, Type B	613.000	CY	170.00	175.00	80.00
3300	605-Y002	Impervious Material, Type D	1,059.000	CY	150.00	65.00	35.50
3310	803-C002	14" x 14" Prestressed Concrete Piling	8,295.000	LF	90.00	100.00	72.50
3320	803-D002	HP 12 x 53 Steel Piling	4,816.000	LF	107.20	45.00	86.00
3330	803-D006	HP 14 x 73 Steel Piling	7,608.000	LF	135.79	45.00	112.00
3340	803-D007	HP 14 x 89 Steel Piling	17,688.000	LF	155.80	35.00	136.00
3350	803-P015	24" Steel Pipe Piling, Wall Thickness 0.625"	5,425.000	LF	328.74	110.00	329.50
3360	804-C188	80' Prestressed Concrete Beam, Type FIB-36	1,272.000	LF	582.76	465.00	397.50
3370	804-C195	85' Prestressed Concrete Beam, Type FIB-36	1,352.000	LF	582.76	460.00	395.50

Add 2 Lanes to I-55 from SR 463 to Gluckstadt Road, & Mill & Overlay approximately 0.77 miles on I-55 from Gluckstadt Road north, known as Federal Aid Project Nos. STP-0055-02(271) / 108168301 & STP-0055-02(275) / 108168302 in Madison County.					Necaise Brothers Construction Co., Inc.	W. G. Yates & Sons Construction Company	Hemphill Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$132,117,148.65					\$195,952,648.70	\$208,867,889.53	\$284,032,160.00
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
3380	804-C208	60' Prestressed Concrete Beam, Type FIB-36	1,904.000	LF	582.76	485.00	393.00
3390	804-C274	40' Prestressed Concrete Beam, Type FIB-36	1,264.000	LF	582.76	505.00	407.50
3400	805-A001	Reinforcement	1,081,334.000	LBS	2.18	2.81	2.00
3410	805-C001	Reinforcement, Corrosion Resistant	22,208.000	LBS	4.29	4.80	4.00
3420	813-A003	Concrete Railing, 42"	1,480.000	LF	217.46	200.00	169.50
3430	815-A007	Loose Riprap, Size 300	6,937.000	TON	122.87	125.00	150.00
3440	815-E001	Geotextile under Riprap	6,383.000	SY	5.35	6.00	4.50
3460	907-803-I002	PDA Test Pile, Concrete Pile	2.000	EA	14,578.00	15,000.00	9,193.50
3470	907-803-I003	PDA Test Pile, HP Steel Pile	23.000	EA	12,148.00	15,000.00	9,957.00
3480	907-803-I004	PDA Test Pile, Steel Pipe Pile	2.000	EA	20,010.00	50,000.00	38,271.00
3490	907-803-J001	Pile Restrike	27.000	EA	3,573.00	3,000.00	3,418.50
3500	907-804-A001	Bridge Concrete, Class BDX	1,668.000	CY	1,786.00	2,500.00	1,857.00
3510	907-804-A002	Bridge Concrete, Class AA	882.000	CY	1,786.00	2,500.00	1,798.00
3520	907-804-A003	Bridge Concrete, Class B	4,726.000	CY	715.00	2,000.00	912.00
3530	907-823-A001	Preformed Joint Seal, Type I	642.000	LF	40.49	35.00	32.00