

Mill & Overlay approximately 0.5 miles East of US 61, known as State Project No. SP-0011-01(078) / 110047301 in Washington County.					APAC - Mississippi, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,899,026.10					\$2,080,971.15		
Ref#	Item	Item Description	Item Qnty	Units	1		
0010	202-B007	Removal of Asphalt Pavement, All Depths	84.000	SY	160.00		
0020	202-B073	Removal of Concrete Pavement, All Depths	9.000	SY	60.00		
0030	202-B136	Removal of Guard Rail	316.000	LF	10.40		
0040	202-B240	Removal of Traffic Stripe	1,100.000	LF	4.00		
0050	203-G002	Excess Excavation, LVM, AH	15.000	CY	5.00		
0060	209-A005	Geotextile Stabilization, Type V, Non-Woven	141.000	SY	15.00		
0070	304-D002	Granular Material, Crushed Stone	300.000	TON	106.65		
0080	406-D003	Fine Milling of Bituminous Pavement, All Depths	5,800.000	TON	33.35		
0090	503-C010	Saw Cut, Full Depth	378.000	LF	27.00		
0100	606-B001	Guard Rail, Class A, Type 1	113.000	LF	34.20		
0110	606-C003	Guard Rail, Cable Anchor, Type 1	2.000	EA	2,072.55		
0120	606-D012	Guard Rail, Bridge End Section, Type D Modified	1.000	EA	2,849.75		
0130	606-E007	Guard Rail, Terminal End Section, Non-Flared	3.000	EA	4,093.30		
0140	618-B001	Additional Construction Signs	1.000	SF	10.00		
0150	619-A1001	Temporary Traffic Stripe, Continuous White	6.000	MI	2,000.00		
0160	619-A2001	Temporary Traffic Stripe, Continuous Yellow	5.000	MI	2,000.00		
0170	619-A3001	Temporary Traffic Stripe, Skip White	4.000	MI	2,000.00		
0180	619-A5001	Temporary Traffic Stripe, Detail	7,500.000	LF	0.40		
0190	619-A6002	Temporary Traffic Stripe, Legend	500.000	LF	2.00		
0200	620-A001	Mobilization	1.000	LS	145,000.00		
0210	630-F006	Delineators, Guard Rail, White	11.000	EA	31.10		
0220	630-G005	Type 3 Object Markers, OM-3R or OM-3L, Post Mounted	2.000	EA	139.90		
0230	907-403-A013	9.5-mm, HT, Asphalt Pavement	5,800.000	TON	162.60		
0240	907-403-A015	9.5-mm, ST, Asphalt Pavement	1,225.000	TON	243.00		
0250	907-403-B006	19-mm, ST, Asphalt Pavement, Leveling	57.000	TON	200.00		
0260	907-407-A001	Asphalt for Tack Coat	6,000.000	GAL	4.10		

Mill & Overlay approximately 0.5 miles East of US 61, known as State Project No. SP-0011-01(078) / 110047301 in Washington County.					APAC - Mississippi, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,899,026.10					\$2,080,971.15		
Ref#	Item	Item Description	Item Qnty	Units	1		
0270	907-413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	4,300.000	LF	3.00		
0280	907-420-A001	Undersealing	10,000.000	LBS	5.00		
0290	907-609-F002	Prefabricated Curb	565.000	LF	73.50		
0300	907-618-A001	Maintenance of Traffic	1.000	LS	100,000.00		
0310	907-619-E3001	Changeable Message Sign	2.000	EA	4,830.00		
0320	907-626-A010	6" Thermoplastic Traffic Stripe, Skip White	4.000	MI	4,000.00		
0330	907-626-B006	6" Thermoplastic Traffic Stripe, Continuous White	3.000	MI	7,900.00		
0340	907-626-E005	6" Thermoplastic Traffic Stripe, Continuous Yellow	3.000	MI	7,900.00		
0350	907-626-G004	Thermoplastic Detail Stripe, White	11,000.000	LF	3.00		
0360	907-626-G005	Thermoplastic Detail Stripe, Yellow	5,100.000	LF	3.00		
0370	907-626-H009	Thermoplastic Legend, White	115.000	SF	8.00		
0380	907-626-H010	Thermoplastic Legend, White	1,000.000	LF	4.00		
0390	907-627-J001	Two-Way Clear Reflective High Performance Raised Markers	200.000	EA	9.00		
0400	907-627-K001	Red-Clear Reflective High Performance Raised Markers	1,000.000	EA	9.00		
0410	907-627-L001	Two-Way Yellow Reflective High Performance Raised Markers	50.000	EA	9.00		