

SECTION 905 -- PROPOSAL (CONTINUED)

I (We) hereby certify by digital signature and electronic submission via Bid Express of the Section 905 proposal below, that all certifications, disclosures and affidavits incorporated herein are deemed to be duly executed in the aggregate, fully enforceable and binding upon delivery of the bid proposal. I (We) further acknowledge that this certification shall not extend to the bid bond or alternate security which must be separately executed for the benefit of the Commission. This signature does not cure deficiencies in any required certifications, disclosures and/or affidavits. I (We) also acknowledge the right of the Commission to require full and final execution on any certification, disclosure or affidavit contained in the proposal at the Commission's election upon award. Failure to so execute at the Commission's request within the time allowed in the Standard Specifications for execution of all contract documents will result in forfeiture of the bid bond or alternate security.

Bidder acknowledges receipt of and has added to and made a part of the proposal and contract documents the following addendum (addenda):

ADDENDUM NO.	<u>1</u>	DATED	<u>10/19/2026</u>	ADDENDUM NO.	_____	DATED	_____
ADDENDUM NO.	_____	DATED	_____	ADDENDUM NO.	_____	DATED	_____
ADDENDUM NO.	_____	DATED	_____	ADDENDUM NO.	_____	DATED	_____

Number

Description

- 1 Revised Bid Items; Revised Plan Sheet Nos. RVP-1, 10, & 11;
Amendment EBSx Download Required.

TOTAL ADDENDA: 1

(Must agree with total addenda issued prior to opening of bids)

Respectfully Submitted,

DATE _____

Contractor

BY _____

Signature

TITLE _____

ADDRESS _____

CITY, STATE, ZIP _____

PHONE _____

FAX _____

E-MAIL _____

(To be filled in if a corporation)

Our corporation is chartered under the Laws of the State of _____ and the names,
titles and business addresses of the executives are as follows:

President

Address

Secretary

Address

Treasurer

Address

The following is my (our) itemized proposal.

IM-0059-01(128)/ 108588301000

Pearl River County(ies)

Revised 01/26/2016

Mill & Overlay approximately 13.7 miles of I-59 from 0.5 miles north of the McNeil Exit to south of MS 26, known as Federal Aid Project No. IM-0059-01(128) / 108588301 in Pearl River County.

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
Roadway Items					
0010	201-D001		1,257	Station	Random Clearing
0020	202-A001		1	Lump Sum	Removal of Obstructions
0030	202-B006		7,180	Square Yard	Removal of Asphalt Paved Shoulders, All Depths
0040	202-B007		2,475	Square Yard	Removal of Asphalt Pavement, All Depths
0050	202-B067		110	Square Yard	Removal of Concrete Pavement Punchouts, 8" Depth
0060	202-B136		14,221	Linear Feet	Removal of Guard Rail
0070	202-B213		4	Each	Removal of Sign
0080	202-B214		4	Each	Removal of Sign Footing
0090	202-B240		17,117	Linear Feet	Removal of Traffic Stripe
0100	406-D001		651,606	Square Yard	Fine Milling of Bituminous Pavement, All Depths
0110	406-E002		1,245	Square Yard	Fine Milling of Concrete Pavement, All Depths
0120	413-D002		7,196	Linear Feet	Cleaning and Filling Joints
0130	423-A001		53	Mile	Rumble Strips, Ground In
0140	501-D001		60	Linear Feet	Expansion Joints, With Dowels
0150	503-A001	(C)	110	Square Yard	8" and Variable Continuously Reinforced Concrete Pavement, Broom Finish
0160	503-B001		80	Linear Feet	Saw Cut, Longitudinal Joints
0170	503-C010		16,297	Linear Feet	Saw Cut, Full Depth
0180	503-E002		40	Each	Tie Bars, No. 5 Deformed Drilled and Epoxied or Grouted
0190	503-F002		120	Each	1" Smooth Dowel Bars, Drilled & Epoxied or Grouted
0200	606-B003		11,556	Linear Feet	Guard Rail, Class A, Type 1, 'W' Beam, Metal Post
0210	606-C001		12	Each	Guard Rail, Cable Anchor Type 1, Metal Post
0220	606-D005		4	Each	Guard Rail, Bridge End Section, Type A
0230	606-D023		16	Each	Guard Rail, Bridge End Section, Type I, Metal Post
0240	606-E005		12	Each	Guard Rail, Terminal End Section, Flared
0250	606-E007		24	Each	Guard Rail, Terminal End Section, Non-Flared
0260	615-A005	(S)	128	Linear Feet	Concrete Pier Protection Barrier, 32"
0270	615-A006	(S)	663	Linear Feet	Concrete Pier Protection Barrier, 42"
0280	615-B001	(S)	500	Linear Feet	Precast Concrete Median Barrier
0290	618-B001		1	Square Feet	Additional Construction Signs [\$10.00]
0300	619-A1001		29	Mile	Temporary Traffic Stripe, Continuous White
0310	619-A2001		30	Mile	Temporary Traffic Stripe, Continuous Yellow
0320	619-A3001		28	Mile	Temporary Traffic Stripe, Skip White

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
0330	619-A4001		607	Linear Feet	Temporary Traffic Stripe, Skip Yellow
0340	619-A5001		10,566	Linear Feet	Temporary Traffic Stripe, Detail
0350	619-A6002		332	Linear Feet	Temporary Traffic Stripe, Legend
0360	619-F2001		500	Linear Feet	Remove and Reset Concrete Median Barrier, Precast
0370	619-J1005		2	Each	Impact Attenuator, 70 MPH
0380	619-J3001		2	Each	Remove and Reset Impact Attenuator
0390	620-A001		1	Lump Sum	Mobilization
0400	630-F006		246	Each	Delineators, Guard Rail, White
0410	630-F007		90	Each	Delineators, Guard Rail, Yellow
0420	630-G005		22	Each	Type 3 Object Markers, OM-3R or OM-3L, Post Mounted
0430	907-402-A002	(BA1)	21,601	Ton	Open Graded Friction Course, 9.5-mm Mixture
0440	907-402-B001	(A3)	32,729	Gallon	Bituminous Tack Coat
0450	907-403-A003	(BA1)	90	Ton	12.5-mm, ST, Asphalt Pavement
0460	907-403-A015	(BA1)	17,715	Ton	9.5-mm, ST, Asphalt Pavement
0470	907-403-S001		55	Mile	Joint Sealant
0480	907-405-A001	(BA1)	36,722	Ton	Stone Matrix Asphalt, 9.5 mm Mixture
0490	907-407-A001	(A2)	31,527	Gallon	Asphalt for Tack Coat
0500	907-503-D001		9	Cubic Yard	Concrete for Base Repair
0510	907-618-A001		1	Lump Sum	Maintenance of Traffic
0520	907-618-M2001		2,000	Hours	Work Zone Law Enforcement [\$60.00]
0530	907-619-E3001		2	Each	Changeable Message Sign
0540	907-626-A010		27	Mile	6" Thermoplastic Traffic Stripe, Skip White
0550	907-626-C014		29	Mile	6" Thermoplastic Edge Stripe, Continuous White
0560	907-626-D006		607	Linear Feet	6" Thermoplastic Traffic Stripe, Skip Yellow
0570	907-626-F005		30	Mile	6" Thermoplastic Edge Stripe, Continuous Yellow
0580	907-626-G004		9,818	Linear Feet	Thermoplastic Detail Stripe, White
0590	907-626-G005		748	Linear Feet	Thermoplastic Detail Stripe, Yellow
0600	907-626-H010		332	Linear Feet	Thermoplastic Legend, White
0610	907-627-K001		3,894	Each	Red-Clear Reflective High Performance Raised Markers
0620	907-627-L001		61	Each	Two-Way Yellow Reflective High Performance Raised Markers
0630	907-627-M001		1,812	Each	One-Way Clear Reflective High Performance Raised Markers
0640	907-627-N001		1,812	Each	One-Way Yellow Reflective High Performance Raised Markers
0650	907-630-O004		2	Each	Remove and Reset Sign, All Sizes

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
ALTERNATE GROUP AA NUMBER 1					
0660	304-F001	(GT)	1,006	Ton	3/4" and Down Crushed Stone Base
ALTERNATE GROUP AA NUMBER 2					
0670	304-F002	(GT)	1,006	Ton	Size 610 Crushed Stone Base
ALTERNATE GROUP AA NUMBER 3					
0680	304-F003	(GT)	1,006	Ton	Size 825B Crushed Stone Base
ALTERNATE GROUP BB NUMBER 1					
0690	907-628-G003		1,592	Linear Feet	6" High Performance Cold Plastic Traffic Stripe, Skip White
0700	907-628-H005		7,904	Linear Feet	6" High Performance Cold Plastic Traffic Stripe, Continuous White
0710	907-628-I004		264	Linear Feet	6" High Performance Cold Plastic Traffic Stripe, Skip Yellow
0720	907-628-J003		7,357	Linear Feet	6" High Performance Cold Plastic Traffic Stripe, Continuous Yellow
ALTERNATE GROUP BB NUMBER 2					
0730	907-624-A002		1,592	Linear Feet	6" Inverted Profile Thermoplastic Traffic Stripe, Skip White
0740	907-624-B002		7,904	Linear Feet	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous White
0750	907-624-C001		264	Linear Feet	6" Inverted Profile Thermoplastic Traffic Stripe, Skip Yellow
0760	907-624-D002		7,357	Linear Feet	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous Yellow

SHEET NO.

DESIGNED BY: DISTRICT 6
DETAILED BY: MB
CHECKED BY: MB
DATE: 8/26/2026

FMS CON: 108588/301000
PROJECT NO.: IM-0059-01(128)
COUNTRY: PEARL_RIVER

FMS CON: 108588/301000	PROJECT NO.: IM-0059-01(128)	COUNTRY: PEARL_RIVER
------------------------	------------------------------	----------------------

FMS CON: 108588/301000
PROJECT NO.: IM-0059-01(128)
COUNTRY: PEARL_RIVER

DESIGNED BY: DISTRICT 6
DETAILED BY: MB
CHECKED BY: MB
DATE: 8/26/2026

DESIGNED BY: DISTRICT 6
DETAILED BY: MB
CHECKED BY: MB
DATE: 8/26/2026

DESIGNED BY: DISTRICT 6
DETAILED BY: MB
CHECKED BY: MB
DATE: 8/26/2026

ADDENDUM

[illegible]

REV. NO.	DATE	1ST ORDER	ADDENDUM	2ND ORDER	INITIALS	SHEET ID.	DESCRIPTION
----------	------	-----------	----------	-----------	----------	-----------	-------------

REV. NO.	DATE	1ST ORDER	ADDENDUM	2ND ORDER	INITIALS	SHEET ID.	DESCRIPTION
----------	------	-----------	----------	-----------	----------	-----------	-------------

REV. NO.	DATE	1ST ORDER	ADDENDUM	2ND ORDER	INITIALS	SHEET ID.	DESCRIPTION
----------	------	-----------	----------	-----------	----------	-----------	-------------

REV. NO.	DATE	1ST ORDER	ADDENDUM	2ND ORDER	INITIALS	SHEET ID.	DESCRIPTION
----------	------	-----------	----------	-----------	----------	-----------	-------------

REV. NO.	DATE	1ST ORDER	ADDENDUM	2ND ORDER	INITIALS	SHEET ID.	DESCRIPTION
----------	------	-----------	----------	-----------	----------	-----------	-------------

REV. NO.	DATE	1ST ORDER	ADDENDUM	2ND ORDER	INITIALS	SHEET ID.	DESCRIPTION
----------	------	-----------	----------	-----------	----------	-----------	-------------

REV. NO.	DATE	1ST ORDER	ADDENDUM	2ND ORDER	INITIALS	SHEET ID.	DESCRIPTION
----------	------	-----------	----------	-----------	----------	-----------	-------------

REV. NO.	DATE	1ST ORDER	ADDENDUM	2ND ORDER	INITIALS	SHEET ID.	DESCRIPTION
----------	------	-----------	----------	-----------	----------	-----------	-------------



ADDENDUM

DESIGNED BY: DISTRICT 6

CHECKED BY: MB

CHECKED BY: MB

DATE: 8/26/2026

FMS CON: 108588/301000

PROJECT NO.: IM-0059-01(128)

COUNTY: PEARL_RIVER

SUMMARY OF QUANTITIES

SHEET ID
SQ-1

SHEET NO.
10

- ① 185 tons for ramp islands, 505 tons for guard rail, 316 tons as needed on ramp shoulders
- ② Includes removal of all w-beam, block outs, hardware, terminal end sections, cable anchors, and bridge end sections.
- ③ Includes removal and disposal of water barriers

SUMMARY OF QUANTITIES (SHEET 1)			PEARL RIVER : 108588-301000	
PAY ITEM NO.	PAY ITEM	UNIT	Prelim	Final
201-D001	Random Clearing	STA	1,257	
202-A001	Removal of Obstructions	LS	1	③
202-B006	Removal of Asphalt Paved Shoulders, All Depths	SY	7,180	
202-B007	Removal of Asphalt Pavement, All Depths	SY	2,475	
202-B067	Removal of Concrete Pavement Punchouts, 8" Depth	SY	110	
202-B136	Removal of Guard Rail	LF	14,221	②
202-B213	Removal of Sign	EA	4	
202-B214	Removal of Sign Footing	EA	4	
202-B240	Removal of Traffic Stripe	LF	17,117	
304-F001	3/4" and Down Crushed Stone Base	TON	1,006	①
	OR			
304-F002	Size 610 Crushed Stone Base	TON	1,006	①
	OR			
304-F003	Size 825B Crushed Stone Base	TON	1,006	①
907-402-A002	Open Graded Friction Course, 9.5-mm Mixture	TON	21,601	
907-402-B001	Bituminous Tack Coat	GAL	32,729	
907-403-A003	12.5-mm, ST, Asphalt Pavement	TON	90	
907-403-A015	9.5-mm, ST, Asphalt Pavement	TON	17,715	
907-403-S001	Joint Sealant	MI	55	
907-405-A001	Stone Matrix Asphalt, 9.5 mm Mixture	TON	36,772	
406-D001	Fine Milling of Bituminous Pavement, All Depths	SY	651,606	
406-E002	Fine Milling of Concrete Pavement, All Depths	SY	1,245	
907-407-A001	Asphalt for Tack Coat	GAL	31,527	
413-D002	Cleaning and Filling Joints	LF	7,196	
423-A001	Rumble Strips, Ground In	MI	53	
501-D001	Expansion Joints, With Dowels	LF	60	
503-A001	8" and Variable Continuously Reinforced Concrete Pavement, Broom Finish	SY	110	
503-B001	Saw Cut, Longitudinal Joints	LF	80	
503-C010	Saw Cut, Full Depth	LF	16,297	
907-503-D001	Concrete for Base Repair	CY	9	
503-E002	Tie Bars, No. 5 Deformed Drilled and Epoxied or Grouted	EA	40	
503-F002	1" Smooth Dowel Bars, Drilled & Epoxied or Grouted	EA	120	
606-B003	Guard Rail, Class A, Type 1, 'W' Beam, Metal Post	LF	11,556	
606-C001	Guard Rail, Cable Anchor Type 1, Metal Post	EA	12	
606-D005	Guard Rail, Bridge End Section, Type A	EA	4	
606-D023	Guard Rail, Bridge End Section, Type 1, Metal Post	EA	16	
606-E005	Guard Rail, Terminal End Section, Flared	EA	12	
606-E007	Guard Rail, Terminal End Section, Non-flared	EA	24	
615-A005	Concrete Pier Protection Barrier, 32"	LF	128	
615-A006	Concrete Pier Protection Barrier, 42"	LF	663	
615-B001	Precast Concrete Median Barrier	LF	500	
907-618-A001	Maintenance of Traffic	LS	1	
618-B001	Additional Construction Signs	SF	1	
907-618-M2001	Work Zone Law Enforcement	HRS	2,000	
619-A1001	Temporary Traffic Stripe, Continuous White	MI	29	
619-A2001	Temporary Traffic Stripe, Continuous Yellow	MI	30	



ADDENDUM

DESIGNED BY: DISTRICT 6
DETAILED BY: MB
CHECKED BY: MB
DATE: 8/26/2026

FMS CON: 108588/301000
PROJECT NO.: IM-0059-01(128)
COUNTY: PEARL_RIVER

SUMMARY OF QUANTITIES

SHEET ID
SQ-2
SHEET NO.
11

REVISIONS		DATE	BY
A	08/30/26	MBB	

① Includes footings

SUMMARY OF QUANTITIES (SHEET 2)			
PAY ITEM NO.	PAY ITEM	UNIT	PEARL RIVER : 108588-301000 Prelim Final
619-A3001	Temporary Traffic Stripe, Skip White	MI	28
619-A4001	Temporary Traffic Stripe, Skip Yellow	LF	607
619-A5001	Temporary Traffic Stripe, Detail	LF	10,566
619-A6002	Temporary Traffic Stripe, Legend	LF	332
907-619-E3001	Changeable Message Sign	EA	2
619-F2001	Remove and Reset Concrete Median Barrier, Precast	LF	500
619-J1005	Impact Attenuator, 70 MPH	EA	2
619-J3001	Remove and Reset Impact Attenuator	EA	2
620-A001	Mobilization	LS	1
907-624-A002	6" Inverted Profile Thermoplastic Traffic Stripe, Skip White	LF	1,592
907-624-B002	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous White	LF	7,904
907-624-C001	6" Inverted Profile Thermoplastic Traffic Stripe, Skip Yellow	LF	264
907-624-D002	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous Yellow	LF	7,357
907-626-A010	6" Thermoplastic Traffic Stripe, Skip White	MI	27
907-626-C014	6" Thermoplastic Edge Stripe, Continuous White	MI	29
907-626-D006	6" Thermoplastic Traffic Stripe, Skip Yellow	LF	607
907-626-F005	6" Thermoplastic Edge Stripe, Continuous Yellow	MI	30
907-626-G004	Thermoplastic Detail Stripe, White	LF	9,818
907-626-G005	Thermoplastic Detail Stripe, Yellow	LF	748
907-626-H010	Thermoplastic Legend, White	LF	332
907-627-K001	Red-Clear Reflective High Performance Raised Markers	EA	3,894
907-627-L001	Two-Way Yellow Reflective High Performance Raised Markers	EA	61
907-627-M001	One-Way Clear Reflective High Performance Raised Markers	EA	1,812
907-627-N001	One-Way Yellow Reflective High Performance Raised Markers	EA	1,812
907-628-G003	6" High Performance Cold Plastic Traffic Stripe, Skip White	LF	1,592
907-628-H005	6" High Performance Cold Plastic Traffic Stripe, Continuous White	LF	7,904
907-628-I004	6" High Performance Cold Plastic Traffic Stripe, Skip Yellow	LF	264
907-628-J003	6" High Performance Cold Plastic Traffic Stripe, Continuous Yellow	LF	7,357
630-F006	Delineators, Guard Rail, White	EA	246
630-F007	Delineators, Guard Rail, Yellow	EA	90
630-G005	Type 3 Object Markers, OM-3R or OM-3., Post Mounted	EA	22
907-630-O004	Remove and Reset Sign, All Sizes	EA	2

①