

SECTION 905 -- PROPOSAL (CONTINUED)

I (We) hereby certify by digital signature and electronic submission via Bid Express of the Section 905 proposal below, that all certifications, disclosures and affidavits incorporated herein are deemed to be duly executed in the aggregate, fully enforceable and binding upon delivery of the bid proposal. I (We) further acknowledge that this certification shall not extend to the bid bond or alternate security which must be separately executed for the benefit of the Commission. This signature does not cure deficiencies in any required certifications, disclosures and/or affidavits. I (We) also acknowledge the right of the Commission to require full and final execution on any certification, disclosure or affidavit contained in the proposal at the Commission's election upon award. Failure to so execute at the Commission's request within the time allowed in the Standard Specifications for execution of all contract documents will result in forfeiture of the bid bond or alternate security.

Bidder acknowledges receipt of and has added to and made a part of the proposal and contract documents the following addendum (addenda):

ADDENDUM NO.	<u>1</u>	DATED	<u>10/19/2026</u>	ADDENDUM NO.	_____	DATED	_____
ADDENDUM NO.	_____	DATED	_____	ADDENDUM NO.	_____	DATED	_____
ADDENDUM NO.	_____	DATED	_____	ADDENDUM NO.	_____	DATED	_____

Number

Description

1 Revised Bid Items; Amendment EBSx Download Required.

TOTAL ADDENDA: 1

(Must agree with total addenda issued prior to opening of bids)

Respectfully Submitted,

DATE _____

Contractor

BY _____

Signature

TITLE _____

ADDRESS _____

CITY, STATE, ZIP _____

PHONE _____

FAX _____

E-MAIL _____

(To be filled in if a corporation)

Our corporation is chartered under the Laws of the State of _____ and the names, titles and business addresses of the executives are as follows:

President

Address

Secretary

Address

Treasurer

Address

The following is my (our) itemized proposal.

IM-0059-02(116)/ 109253301000 & IM-0059-02(123)/ 110070301000

Clarke & Jasper County(ies)

Revised 01/26/2016

Fog Seal approximately 6.2 miles of I-59 from 0.8 mile north of CR 39 to the Jasper/Clarke County Line & Replacing OGFC on approximately 6.45 miles of I-59 from the Jasper County north approximately 6.45 miles, known as Federal Aid Project Nos. IM-0059-02(123) / 110070301 & IM-0059-02(116) / 109253301 in Jasper & Clarke Counties.

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
Roadway Items					
0010	201-D001		769	Station	Random Clearing
0020	202-B006		5,069	Square Yard	Removal of Asphalt Paved Shoulders, All Depths
0030	202-B007		54	Square Yard	Removal of Asphalt Pavement, All Depths
0040	202-B067		70	Square Yard	Removal of Concrete Pavement Punchouts, 8" Depth
0050	202-B136		7,500	Linear Feet	Removal of Guard Rail
0060	202-B240		4,721	Linear Feet	Removal of Traffic Stripe
0070	406-D001		214,707	Square Yard	Fine Milling of Bituminous Pavement, All Depths
0080	501-D001		48	Linear Feet	Expansion Joints, With Dowels
0090	503-B001		24	Linear Feet	Saw Cut, Longitudinal Joints
0100	503-C010		11,082	Linear Feet	Saw Cut, Full Depth
0110	503-E002		26	Each	Tie Bars, No. 5 Deformed Drilled and Epoxied or Grouted
0120	503-F002		36	Each	1" Smooth Dowel Bars, Drilled & Epoxied or Grouted
0130	606-B003		5,782	Linear Feet	Guard Rail, Class A, Type 1, 'W' Beam, Metal Post
0140	606-C003		10	Each	Guard Rail, Cable Anchor, Type 1
0150	606-D005		16	Each	Guard Rail, Bridge End Section, Type A
0160	606-D022		2	Each	Guard Rail, Bridge End Section, Type I
0170	606-E005		28	Each	Guard Rail, Terminal End Section, Flared
0180	618-B001		2	Square Feet	Additional Construction Signs [\$10.00]
0190	619-A1001		26	Mile	Temporary Traffic Stripe, Continuous White
0200	619-A1002		720	Linear Feet	Temporary Traffic Stripe, Continuous White
0210	619-A2001		26	Mile	Temporary Traffic Stripe, Continuous Yellow
0220	619-A2002		720	Linear Feet	Temporary Traffic Stripe, Continuous Yellow
0230	619-A3001		26	Mile	Temporary Traffic Stripe, Skip White
0240	619-A3002		720	Linear Feet	Temporary Traffic Stripe, Skip White
0250	619-A5001		4,768	Linear Feet	Temporary Traffic Stripe, Detail
0260	619-A6004		760	Linear Feet	Temporary Traffic Stripe, Legend, Paint
0270	619-F3001		154	Each	Delineators, Guard Rail, White
0280	619-F3002		94	Each	Delineators, Guard Rail, Yellow
0290	620-A001		1	Lump Sum	Mobilization
0300	630-G005		28	Each	Type 3 Object Markers, OM-3R or OM-3L, Post Mounted
0310	907-402-A002	(BA1)	10,910	Ton	Open Graded Friction Course, 9.5-mm Mixture

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
0320	907-402-B001	(A3)	23,134	Gallon	Bituminous Tack Coat
0330	907-403-D007	(BA1)	256	Ton	9.5-mm, HT, Asphalt Pavement, Polymer Modified
0340	907-407-A001	(A2)	152	Gallon	Asphalt for Tack Coat
0350	907-413-E001		576	Linear Feet	Sawing and Sealing Transverse Joints in Asphalt Pavement
0360	907-428-D001	(A2)	38,859	Gallon	Bio-Based Fog Seal with Rejuvenator
0370	907-501-A002	(C)	70	Square Yard	8" Reinforced Cement Concrete Pavement, Broom Finish
0380	907-503-D001		15	Cubic Yard	Concrete for Base Repair
0390	907-618-A001		1	Lump Sum	Maintenance of Traffic
0400	907-618-M2001		360	Hours	Work Zone Law Enforcement [\$60.00]
0410	907-619-E3001		4	Each	Changeable Message Sign
0420	907-626-A010		26	Mile	6" Thermoplastic Traffic Stripe, Skip White
0430	907-626-C014		27	Mile	6" Thermoplastic Edge Stripe, Continuous White
0440	907-626-F005		27	Mile	6" Thermoplastic Edge Stripe, Continuous Yellow
0450	907-626-G004		4,768	Linear Feet	Thermoplastic Detail Stripe, White
0460	907-626-H010		760	Linear Feet	Thermoplastic Legend, White
0470	907-627-K001		4,256	Each	Red-Clear Reflective High Performance Raised Markers
0480	907-627-M001		1,690	Each	One-Way Clear Reflective High Performance Raised Markers
0490	907-627-N001		1,690	Each	One-Way Yellow Reflective High Performance Raised Markers
ALTERNATE GROUP AA NUMBER 1					
0500	304-F001	(GT)	845	Ton	3/4" and Down Crushed Stone Base
ALTERNATE GROUP AA NUMBER 2					
0510	304-F002	(GT)	845	Ton	Size 610 Crushed Stone Base
ALTERNATE GROUP AA NUMBER 3					
0520	304-F003	(GT)	845	Ton	Size 825B Crushed Stone Base
ALTERNATE GROUP BB NUMBER 1					
0530	907-628-G003		1,605	Linear Feet	6" High Performance Cold Plastic Traffic Stripe, Skip White
0540	907-628-H005		1,605	Linear Feet	6" High Performance Cold Plastic Traffic Stripe, Continuous White
0550	907-628-J003		1,605	Linear Feet	6" High Performance Cold Plastic Traffic Stripe, Continuous Yellow
ALTERNATE GROUP BB NUMBER 2					
0560	907-624-A002		1,605	Linear Feet	6" Inverted Profile Thermoplastic Traffic Stripe, Skip White
0570	907-624-B002		1,605	Linear Feet	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous White
0580	907-624-D002		1,605	Linear Feet	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous Yellow