Bridge Replacement on SR 28 between the Copiah County Line & Pinola (Bridge Nos. 72.7 & 73.6) & over Tanyard Creek (Bridge No. 77.6), known as Federal Aid Project Nos. STBG-0013-02(034) / 100881301 & BR-0013-02(029) / 106971301 in Simpson County.					Chris Albritton Construction Company, Inc.		
		MISSISSIPPI DEPARTMENT OF TRANSPORTATION: $25,434,899.27			$27,352,217.61		
Ref#	Item	Item Description	Item Qnty	Units	1		
0010	201-B001	Clearing and Grubbing	13.000	ACRE	3,540.00		
0020	202-A001	Removal of Obstructions	1.000	LS	11,800.00		
0030	202-B004	Removal of Asphalt Driveways, All Depths	457.000	SY	5.31		
0040	202-B007	Removal of Asphalt Pavement, All Depths	8,075.000	SY	7.08		
0050	202-B017	Removal of Box Bridge	1.000	EA	14,160.00		
0060	202-B023	Removal of Bridge	2.000	EA	666,700.00		
0070	202-B136	Removal of Guard Rail	1,085.000	LF	5.72		
0080	202-B191	Removal of Pipe, 8" And Above	108.000	LF	11.80		
0090	202-B208	Removal of Riprap	333.000	SY	17.70		
0100	202-B215	Removal of Sign Including Post & Footing	15.000	EA	171.10		
0110	202-B240	Removal of Traffic Stripe	500.000	LF	5.90		
0120	203-A001	Unclassified Excavation, FM, AH	10,239.000	CY	6.79		
0130	203-EX021	Borrow Excavation, AH, FME, Class B9-6	26,843.000	CY	18.33		
0140	203-F001	Channel Excavation, FM	2,116.000	CY	11.80		
0150	203-G001	Excess Excavation, FM, AH	11,001.000	CY	9.50		
0160	206-A001	Structure Excavation	583.000	CY	9.51		
0170	206-B001	Select Material for Undercuts, Contractor Furnished, FM	47.000	CY	194.57		
0180	209-A005	Geotextile Stabilization, Type V, Non-Woven	15,109.000	SY	3.54		
0190	211-B001	Topsoil for Slope Treatment, Contractor Furnished	3,280.000	CY	29.50		
0200	213-C001	Superphosphate	6.000	TON	944.00		
0210	216-A001	Solid Sodding	575.000	SY	8.85		
0220	217-A001	Ditch Liner	693.000	SY	5.90		
0230	219-A001	Watering	12.000	KGAL	20.00		
0240	220-A001	Insect Pest Control	11.000	ACRE	30.00		
0250	221-A001	Concrete Paved Ditch	58.000	CY	1,180.00		
0260	223-A001	Mowing	26.000	ACRE	70.00		

Bridge Replacement on SR 28 between the Copiah County Line & Pinola (Bridge Nos. 72.7 & 73.6) & over Tanyard Creek (Bridge No. 77.6), known as Federal Aid Project Nos. STBG-0013-02(034) / 100881301 & BR-0013-02(029) / 106971301 in Simpson County.					Chris Albritton Construction Company, Inc.		
				MISSISSIPPI DEPARTMENT OF TRANSPORTATION: $25,434,899.27	$27,352,217.61		
Ref#	Item	Item Description	Item Qnty	Units	1		
0270	225-A001	Grassing	13.000	ACRE	1,298.00		
0280	225-B001	Agricultural Limestone	6.000	TON	118.00		
0290	225-C001	Mulch, Vegetative Mulch	25.000	TON	236.00		
0300	226-A001	Temporary Grassing	13.000	ACRE	1,062.00		
0310	236-A008	Silt Basin, Type D	2.000	EA	4,130.00		
0320	237-A002	Wattles, 20"	930.000	LF	7.08		
0330	239-A001	Temporary Slope Drains	1,000.000	LF	11.80		
0340	245-A001	Silt Dike	350.000	LF	11.80		
0350	246-B001	Rockbags	550.000	EA	11.80		
0360	249-A001	Riprap for Erosion Control	605.000	TON	106.79		
0370	249-B001	Remove and Reset Riprap	327.000	CY	47.20		
0380	304-A008	Granular Material, LVM, Class 6, Group D	1,850.000	CY	35.40		
0390	406-D001	Fine Milling of Bituminous Pavement, All Depths	3,193.000	SY	5.31		
0400	423-A001	Rumble Strips, Ground In	3.000	MI	354.00		
0410	501-D001	Expansion Joints, With Dowels	149.000	LF	20.65		
0420	501-K001	Transverse Grooving	71.000	SY	177.00		
0430	602-A001	Reinforcing Steel	6,965.000	LBS	2.66		
0440	603-ALT003	18" Type A Alternate Pipe	144.000	LF	70.45		
0450	603-ALT006	24" Type A Alternate Pipe	320.000	LF	83.99		
0460	603-ALT011	36" Type A Alternate Pipe	48.000	LF	139.64		
0470	603-CA011	18" Reinforced Concrete Pipe, Class III	72.000	LF	96.62		
0480	603-CA026	24" Reinforced Concrete Pipe, Class III	40.000	LF	116.45		
0490	603-CA055	36" Reinforced Concrete Pipe, Class III	200.000	LF	158.08		
0500	603-CA119	72" Reinforced Concrete Pipe, Class III	72.000	LF	492.44		
0510	603-CB003	18" Reinforced Concrete End Section	3.000	EA	973.50		
0520	603-CB004	24" Reinforced Concrete End Section	1.000	EA	1,150.50		

Bridge Replacement on SR 28 between the Copiah County Line & Pinola (Bridge Nos. 72.7 & 73.6) & over Tanyard Creek (Bridge No. 77.6), known as Federal Aid Project Nos. STBG-0013-02(034) / 100881301 & BR-0013-02(029) / 106971301 in Simpson County.					Chris Albritton Construction Company, Inc.		
		MISSISSIPPI DEPARTMENT OF TRANSPORTATION: $25,434,899.27			$27,352,217.61		
Ref#	Item	Item Description	Item Qnty	Units	1		
0530	603-CB006	36" Reinforced Concrete End Section	3.000	EA	1,681.50		
0540	603-CB012	72" Reinforced Concrete End Section	2.000	EA	5,693.50		
0550	604-B001	Gratings	127.000	LBS	7.08		
0560	605-AA001	Geotextile for Subsurface Drainage, Type III	143.000	SY	3.54		
0570	605-O002	4" Perforated Sewer Pipe for Underdrains, SDR 23.5	251.000	LF	11.80		
0580	605-P002	4" Non-perforated Sewer Pipe for Underdrains, SDR 23.5	160.000	LF	11.80		
0590	605-W001	Filter Material for Combination Storm Drain and/or Underdrains,Type A, FM	10.000	CY	118.00		
0600	606-B001	Guard Rail, Class A, Type 1	475.000	LF	38.35		
0610	606-D022	Guard Rail, Bridge End Section, Type I	12.000	EA	4,307.00		
0620	606-E005	Guard Rail, Terminal End Section, Flared	12.000	EA	4,307.00		
0630	607-D004	Barbed Wire Fence, 5 Strands, Galvanized Steel	418.000	LF	16.52		
0640	607-G089	Gate, 12' x 52" Galvanized Metal	1.000	EA	1,123.36		
0650	607-P1007	Line Post, 7' Tee Post Steel	26.000	EA	80.24		
0660	607-P2009	Brace Post, 8' x 6" Timber	13.000	EA	354.00		
0670	607-P2019	Brace Post, 12' x 6" Timber	8.000	EA	431.88		
0680	607-Z001	Concrete Anchors	14.000	EA	71.98		
0690	612-A001	Flowable Fill, Excavatable	10.000	CY	590.00		
0700	615-A024	Concrete Bridge End Barrier, 37.5"	120.000	LF	101.48		
0710	617-A001	Right-of-Way Marker	44.000	EA	708.00		
0720	618-D001	Construction and Removal of Detour	1.000	LS	3,540,000.00		
0730	618-E001	Detour Bridge Piling	4,662.000	LF	97.50		
0740	618-F001	Detour Bridge PDA Test Pile	1.000	LS	35,400.00		
0750	619-A1002	Temporary Traffic Stripe, Continuous White	12,577.000	LF	1.18		
0760	619-A2002	Temporary Traffic Stripe, Continuous Yellow	2,200.000	LF	1.18		
0770	619-A6002	Temporary Traffic Stripe, Legend	216.000	LF	1.18		
0780	619-C7001	Two-Way Yellow Reflective High Performance Raised Marker	6.000	EA	23.60		

Bridge Replacement on SR 28 between the Copiah County Line & Pinola (Bridge Nos. 72.7 & 73.6) & over Tanyard Creek (Bridge No. 77.6), known as Federal Aid Project Nos. STBG-0013-02(034) / 100881301 & BR-0013-02(029) / 106971301 in Simpson County.					Chris Albritton Construction Company, Inc.		
		MISSISSIPPI DEPARTMENT OF TRANSPORTATION: $25,434,899.27			$27,352,217.61		
Ref#	Item	Item Description	Item Qnty	Units	1		
0790	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	198.000	SF	11.80		
0800	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	1,742.000	SF	11.80		
0810	619-F3001	Delineators, Guard Rail, White	12.000	EA	41.30		
0820	619-G4001	Barricades, Type III, Double Faced	132.000	LF	23.60		
0830	619-G4003	Barricades, Type III, Double Faced, Permanent, Red/White	30.000	LF	31.86		
0840	619-G4005	Barricades, Type III, Single Faced	528.000	LF	23.60		
0850	619-G5001	Free Standing Plastic Drums	150.000	EA	47.20		
0860	619-G7001	Warning Lights, Type "B"	37.000	EA	23.60		
0870	619-J1002	Impact Attenuator, 45 MPH	2.000	EA	4,307.00		
0880	619-J2002	Impact Attenuator, 45 MPH, Replacement Package	1.000	EA	2,330.50		
0890	619-K1001	Installation and Removal of Guard Rail, Type I, Class A	100.000	LF	112.10		
0900	619-K4001	Installation and Removal of Guardrail, Terminal End Section	4.000	EA	5,723.00		
0910	620-A001	Mobilization	1.000	LS	2,721,731.90		
0920	621-A001	Field Laboratory	1.000	EA	30,680.00		
0930	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	99.000	SF	25.96		
0940	630-A005	Standard Roadside Signs, Sheet Aluminum, 0.1" Thickness	23.000	SF	23.60		
0950	630-C005	Square Tube Posts, 2.0 lb/ft	186.000	LF	30.68		
0960	630-F006	Delineators, Guard Rail, White	54.000	EA	35.40		
0970	630-G005	Type 3 Object Markers, OM-3R or OM-3L, Post Mounted	12.000	EA	247.80		
0980	699-A001	Roadway Construction Stakes	1.000	LS	708,000.00		
0990	815-A007	Loose Riprap, Size 300	6,807.000	TON	106.79		
1000	815-E001	Geotextile under Riprap	6,404.000	SY	3.54		
1010	815-F002	Sediment Control Stone	394.000	TON	86.73		
1020	907-234-A001	Temporary Silt Fence	6,600.000	LF	3.54		
1030	907-234-C001	Super Silt Fence	1,051.000	LF	17.70		
1040	907-234-F001	Turbidity Barrier	100.000	LF	118.00		

Bridge Replacement on SR 28 between the Copiah County Line & Pinola (Bridge Nos. 72.7 & 73.6) & over Tanyard Creek (Bridge No. 77.6), known as Federal Aid Project Nos. STBG-0013-02(034) / 100881301 & BR-0013-02(029) / 106971301 in Simpson County.					Chris Albritton Construction Company, Inc.		
		MISSISSIPPI DEPARTMENT OF TRANSPORTATION: $25,434,899.27			$27,352,217.61		
Ref#	Item	Item Description	Item Qnty	Units	1		
1050	907-250-A001	Polyacrylamide (PAM)	450.000	LBS	11.80		
1060	907-253-A001	Coir Fiber Baffle	105.000	LF	11.80		
1070	907-403-A002	12.5-mm, MT, Asphalt Pavement	554.000	TON	159.37		
1080	907-403-A003	12.5-mm, ST, Asphalt Pavement	313.000	TON	194.32		
1090	907-403-A005	19-mm, MT, Asphalt Pavement	1,471.000	TON	144.08		
1100	907-403-A006	19-mm, ST, Asphalt Pavement	473.000	TON	157.73		
1110	907-403-A014	9.5-mm, MT, Asphalt Pavement	829.000	TON	173.88		
1120	907-403-A015	9.5-mm, ST, Asphalt Pavement	497.000	TON	170.33		
1130	907-407-A001	Asphalt for Tack Coat	2,417.000	GAL	4.13		
1140	907-413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	222.000	LF	7.08		
1150	907-502-A001	Reinforced Cement Concrete Bridge End Pavement	490.000	SY	430.70		
1160	907-601-A001	Class "B" Structural Concrete	45.000	CY	1,298.00		
1170	907-601-B001	Class "B" Structural Concrete, Minor Structures	9.000	CY	1,298.00		
1180	907-618-A001	Maintenance of Traffic	1.000	LS	1,231,504.40		
1190	907-619-B001	Temporary Portable Rumble Strips	72.000	LF	76.70		
1200	907-619-E3001	Changeable Message Sign	6.000	EA	6,490.00		
1210	907-619-H2003	Traffic Signal, Portable, Type 2B	6.000	EA	10,030.00		
1220	907-626-C013	6" Thermoplastic Edge Stripe, Continuous White	11,441.000	LF	2.07		
1230	907-626-D006	6" Thermoplastic Traffic Stripe, Skip Yellow	1,118.000	LF	3.54		
1240	907-626-E006	6" Thermoplastic Traffic Stripe, Continuous Yellow	10,559.000	LF	2.07		
1250	907-626-G004	Thermoplastic Detail Stripe, White	438.000	LF	7.08		
1260	907-626-H010	Thermoplastic Legend, White	318.000	LF	14.16		
1270	907-627-J001	Two-Way Clear Reflective High Performance Raised Markers	88.000	EA	17.70		
1280	907-627-J001	Two-Way Clear Reflective High Performance Raised Markers , Temporary	178.000	EA	17.70		
1290	907-627-L001	Two-Way Yellow Reflective High Performance Raised Markers	142.000	EA	17.70		
1300	907-906001	Trainees	720.000	HRS	5.00		

Bridge Replacement on SR 28 between the Copiah County Line & Pinola (Bridge Nos. 72.7 & 73.6) & over Tanyard Creek (Bridge No. 77.6), known as Federal Aid Project Nos. STBG-0013-02(034) / 100881301 & BR-0013-02(029) / 106971301 in Simpson County.					Chris Albritton Construction Company, Inc.		
		MISSISSIPPI DEPARTMENT OF TRANSPORTATION: $25,434,899.27			$27,352,217.61		
Ref#	Item	Item Description	Item Qnty	Units	1		
1310	304-F001	3/4" and Down Crushed Stone Base	6,363.000	TON			
1320	304-F002	Size 610 Crushed Stone Base	6,363.000	TON			
1330	304-F003	Size 825B Crushed Stone Base	6,363.000	TON	80.83		
1340	605-W002	Filter Material for Combination Storm Drain and/or Underdrains,Type B, FM	187.000	CY	141.60		
1350	605-W003	Filter Material for Combination Storm Drain and/or Underdrains,Type C, FM	187.000	CY			
1360	501-K001	Transverse Grooving	3,864.000	SY	3.19		
1370	803-D006	HP 14 x 73 Steel Piling	2,325.000	LF	125.66		
1380	803-K010	Drilled Shaft, 72" Diameter	720.000	LF	1,787.70		
1390	803-L006	Test Shaft, 72" Diameter	1.000	EA	627,760.00		
1400	803-M009	Trial Shaft, 72" Diameter	121.000	LF	2,478.00		
1410	803-N001	Exploration	60.000	LF	1.00		
1420	803-O011	Permanent Casing, 72" Diameter	306.000	LF	1,309.80		
1430	803-P001	24" Steel Pipe Piling, Wall Thickness 0.500"	2,040.000	LF	290.28		
1440	803-P003	30" Steel Pipe Piling, Wall Thickness 0.500"	1,465.000	LF	460.20		
1450	804-C188	80' Prestressed Concrete Beam, Type FIB-36	398.000	LF	454.06		
1460	804-C192	100' Prestressed Concrete Beam, Type FIB-36	995.000	LF	454.06		
1470	804-C193	120' Prestressed Concrete Beam, Type FIB-45	717.000	LF	460.20		
1480	804-C236	105' Prestressed Concrete Beam, Type FIB-45	1,045.000	LF	460.20		
1490	805-A001	Reinforcement	401,568.000	LBS	1.91		
1500	805-C001	Reinforcement, Corrosion Resistant	2,632.000	LBS	4.25		
1510	813-A004	Concrete Railing, 36"	2,173.000	LF	101.48		
1520	815-A007	Loose Riprap, Size 300	4,462.000	TON	100.89		
1530	815-E001	Geotextile under Riprap	3,538.000	SY	3.54		
1540	907-803-I003	PDA Test Pile, HP Steel Pile	1.000	EA	29,500.00		
1550	907-803-I004	PDA Test Pile, Steel Pipe Pile	4.000	EA	35,400.00		
1560	907-803-J001	Pile Restrike	5.000	EA	1,180.00		

Bridge Replacement on SR 28 between the Copiah County Line & Pinola (Bridge Nos. 72.7 & 73.6) & over Tanyard Creek (Bridge No. 77.6), known as Federal Aid Project Nos. STBG-0013-02(034) / 100881301 & BR-0013-02(029) / 106971301 in Simpson County.					Chris Albritton Construction Company, Inc.		
		MISSISSIPPI DEPARTMENT OF TRANSPORTATION: $25,434,899.27			$27,352,217.61		
Ref#	Item	Item Description	Item Qnty	Units	1		
1570	907-804-A001	Bridge Concrete, Class BDX	1,288.000	CY	1,298.00		
1580	907-804-A002	Bridge Concrete, Class AA	410.000	CY	1,298.00		
1590	907-804-A002	Bridge Concrete, Class AA 6 ksi closure between beam ends	12.000	CY	1,298.00		
1600	907-804-PP004	Post Tensioning System	1.000	LS	295,000.00		
1610	907-804-PP003	68' Post-Tensioned Concrete Beam, Per Plans	680.000	LF	2,478.00		
1620	907-804-PP015	104' Post-Tensioned Concrete Beam, Per Plans	1,038.000	LF	879.10		
1630	907-804-PP016	118' Post-Tensioned Concrete Beam, Per Plans	590.000	LF	728.06		
1640	907-822-B003	3" Reinforced Elastomeric Molded Rubber Expansion Joint	76.000	LF	1,770.00		
1650	907-823-A001	Preformed Joint Seal, Type I	232.000	LF	37.76		