Add 2 Lanes to I-55 from SR 463 to Gluckstadt Road, & Mill & Overlay approximately 0.77 miles on I-55 from Gluckstadt Road north, known as Federal Aid Project Nos. STP-0055-02(271) / 108168301 & STP-0055-02(275) / 108168302 in Madison County.					T. L. Wallace Construction, Inc.	W. G. Yates & Sons Construction Company	Necaise Brothers Construction Co., Inc.
		MISSISSIPPI DEPARTMENT OF TRANSPORTATION: $179,163,056.40			$187,725,441.40	$193,158,658.00	$202,217,715.43
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
0010	201-B001	Clearing and Grubbing	30.000	ACRE	13,680.00	47,500.00	15,273.36
0020	201-D001	Random Clearing	16.000	STA	2,734.25	5,000.00	2,937.18
0030	202-B007	Removal of Asphalt Pavement, All Depths	2,580.000	SY	17.35	15.00	11.35
0040	202-B017	Removal of Box Bridge	4.000	EA	113,000.00	100,000.00	101,332.86
0050	202-B019	Removal of Box Culvert	39.000	LF	863.25	550.00	500.00
0060	202-B059	Removal of Concrete Median & Island Pavement, All Depths	471.000	SY	44.85	30.00	28.38
0070	202-B060	Removal of Concrete Median Barrier	40.000	LF	213.75	300.00	146.86
0080	202-B061	Removal of Concrete Median Barrier, Precast	11,500.000	LF	20.20	10.00	17.34
0090	202-B063	Removal of Concrete Paved Ditch	121.000	SY	17.60	20.00	34.06
0100	202-B069	Removal of Concrete Pavement w/ Variable Depth Overlay	34,294.000	SY	32.35	25.00	28.38
0110	202-B089	Removal of Curb &/or Curb and Gutter, All Types	721.000	LF	18.05	22.00	23.00
0120	202-B096	Removal of Debris and Sand From Box Culvert, 10-foot and Greater Width	802.000	LF	105.35	100.00	58.74
0130	202-B114	Removal of Debris and Sand From Pipe, All Sizes	100.000	LF	105.35	150.00	58.74
0140	202-B126	Removal of Fence, All Types	40,623.000	LF	6.20	5.00	6.46
0150	202-B150	Removal of Guard Rail Including Post, Blockouts & Hardware	4,679.000	LF	5.50	5.25	5.87
0160	202-B160	Removal of High Mast Lighting Assembly	2.000	EA	11,310.00	10,500.00	11,701.75
0170	202-B162	Removal of Impact Attenuator	3.000	EA	1,313.25	1,500.00	1,468.59
0180	202-B165	Removal of Inlets, All Sizes	8.000	EA	1,557.50	1,500.00	1,135.29
0190	202-B177	Removal of Low Mast Lighting Assembly	13.000	EA	2,168.75	1,450.00	1,603.70
0200	202-B191	Removal of Pipe, 8" And Above	538.000	LF	44.75	30.00	22.70
0210	202-B220	Removal of Sign, Overhead Mounted Including Panels, Trust, and Footings	1.000	EA	15,190.00	13,500.00	14,685.93
0220	202-B225	Removal of Soil Cement Shoulders with Asphalt Overlay	55,594.000	SY	16.45	17.00	17.03
0230	202-B226	Removal of Soil Cement Treated Base, All Depths	34,294.000	SY	8.25	6.00	11.35
0240	202-B226	Removal of Soil Cement Treated Base, All Depths - Milling	14,175.000	SY	11.00	13.00	11.75
0250	202-B240	Removal of Traffic Stripe	6,000.000	LF	4.95	16.00	17.62
0260	202-B273	Removal of Debris and Sand From Box Culvert, 6-foot to Less than 10-foot Width	145.000	LF	105.35	150.00	176.23

Add 2 Lanes to I-55 from SR 463 to Gluckstadt Road, & Mill & Overlay approximately 0.77 miles on I-55 from Gluckstadt Road north, known as Federal Aid Project Nos. STP-0055-02(271) / 108168301 & STP-0055-02(275) / 108168302 in Madison County.					T. L. Wallace Construction, Inc.	W. G. Yates & Sons Construction Company	Necaise Brothers Construction Co., Inc.
		MISSISSIPPI DEPARTMENT OF TRANSPORTATION: $179,163,056.40			$187,725,441.40	$193,158,658.00	$202,217,715.43
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
0270	202-B276	Removal of Debris from Drainage Channel	690.000	LF	105.35	150.00	113.51
0280	203-EX021	Borrow Excavation, AH, FME, Class B9-6	583,811.000	CY	29.60	35.00	30.50
0290	203-F001	Channel Excavation, FM	15,151.000	CY	25.90	20.00	30.00
0300	203-G001	Excess Excavation, FM, AH	498,248.000	CY	23.10	20.00	19.50
0310	206-A001	Structure Excavation	2,935.000	CY	35.70	60.00	40.00
0320	206-B001	Select Material for Undercuts, Contractor Furnished, FM	96.000	CY	160.05	400.00	155.00
0330	209-A005	Geotextile Stabilization, Type V, Non-Woven	279,624.000	SY	2.70	3.00	3.00
0340	211-B001	Topsoil for Slope Treatment, Contractor Furnished	29,750.000	CY	0.01	5.00	5.00
0350	213-C001	Superphosphate	56.000	TON	984.30	915.00	1,057.39
0360	216-A001	Solid Sodding	2,873.000	SY	8.25	8.00	8.81
0370	217-A001	Ditch Liner	2,209.000	SY	2.65	3.00	2.94
0380	219-A001	Watering	59.000	KGAL	20.00	20.00	20.00
0390	220-A001	Insect Pest Control	56.000	ACRE	30.00	30.00	30.00
0400	221-A001	Concrete Paved Ditch	3,548.000	CY	1,312.50	1,200.00	1,481.10
0410	223-A001	Mowing	851.000	ACRE	70.00	70.00	70.00
0420	224-A001	Soil Reinforcing Mat	7,370.000	SY	3.85	4.00	4.11
0430	225-A001	Grassing	111.000	ACRE	1,367.25	1,275.00	1,468.59
0440	225-B001	Agricultural Limestone	56.000	TON	115.60	110.00	129.24
0450	225-C001	Mulch, Vegetative Mulch	222.000	TON	229.70	215.00	246.72
0460	226-A001	Temporary Grassing	111.000	ACRE	1,093.75	1,025.00	1,174.87
0470	236-A008	Silt Basin, Type D	8.000	EA	1.20	7,500.00	8,000.00
0480	237-A002	Wattles, 20"	4,500.000	LF	9.05	6.25	7.05
0490	239-A001	Temporary Slope Drains	2,000.000	LF	0.05	25.00	14.10
0500	245-A001	Silt Dike	2,000.000	LF	0.05	15.00	17.62
0510	246-B002	Rockbags	4,000.000	LF	16.40	15.00	17.62
0520	249-A001	Riprap for Erosion Control	8,000.000	TON	121.70	150.00	116.90

Add 2 Lanes to I-55 from SR 463 to Gluckstadt Road, & Mill & Overlay approximately 0.77 miles on I-55 from Gluckstadt Road north, known as Federal Aid Project Nos. STP-0055-02(271) / 108168301 & STP-0055-02(275) / 108168302 in Madison County.					T. L. Wallace Construction, Inc.	W. G. Yates & Sons Construction Company	Necaise Brothers Construction Co., Inc.
		MISSISSIPPI DEPARTMENT OF TRANSPORTATION: $179,163,056.40			$187,725,441.40	$193,158,658.00	$202,217,715.43
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
0530	304-D002	Granular Material, Crushed Stone	18,150.000	TON	90.85	100.00	97.89
0540	307-B003	6" Soil-Lime-Water Mixing, Class B	118,950.000	SY	8.10	8.00	11.81
0550	307-D001	Lime	1,606.000	TON	836.65	925.00	916.48
0560	307-S001	Bituminous Curing Seal	29,738.000	GAL	5.00	4.50	9.38
0570	308-A001	Cement	1,071.000	TON	300.80	165.00	302.85
0580	308-B003	Soil-Cement-Water Mixing, Optional Mixers, Design Soil	118,950.000	SY	3.45	1.65	1.53
0590	308-S001	Bituminous Curing Seal	29,738.000	GAL	5.00	4.50	9.38
0600	406-D001	Fine Milling of Bituminous Pavement, All Depths	302,705.000	SY	5.35	4.25	5.11
0610	423-A001	Rumble Strips, Ground In	17.000	MI	367.75	625.00	411.21
0620	501-K001	Transverse Grooving	222.000	SY	2.90	3.00	3.23
0630	503-C010	Saw Cut, Full Depth	40,670.000	LF	7.45	7.50	9.38
0640	602-A001	Reinforcing Steel	48,821.000	LBS	1.70	2.75	4.11
0650	603-ALT003	18" Type A Alternate Pipe	72.000	LF	74.80	120.00	124.11
0660	603-CA011	18" Reinforced Concrete Pipe, Class III	1,032.000	LF	82.60	120.00	85.97
0670	603-CA022	18" Reinforced Concrete Pipe, Class V, Jacked or Bored	2,024.000	LF	1,355.25	1,100.00	1,288.72
0680	603-CA026	24" Reinforced Concrete Pipe, Class III	824.000	LF	94.60	150.00	101.26
0690	603-CA038	24" Reinforced Concrete Pipe, Class V, Jacked or Bored	632.000	LF	1,503.25	1,200.00	1,428.68
0700	603-CA040	30" Reinforced Concrete Pipe, Class III	8.000	LF	104.75	275.00	162.76
0710	603-CA055	36" Reinforced Concrete Pipe, Class III	96.000	LF	146.85	300.00	359.54
0720	603-CA065	36" Reinforced Concrete Pipe, Class V, Jacked or Bored	224.000	LF	1,666.50	1,500.00	1,567.33
0730	603-CA066	42" Reinforced Concrete Pipe, Class III	16.000	LF	171.75	350.00	245.80
0740	603-CB003	18" Reinforced Concrete End Section	28.000	EA	1,153.75	1,400.00	2,489.66
0750	603-CB004	24" Reinforced Concrete End Section	20.000	EA	1,208.50	1,800.00	2,642.39
0760	603-CB005	30" Reinforced Concrete End Section	1.000	EA	1,220.50	2,200.00	2,832.76
0770	603-CB006	36" Reinforced Concrete End Section	4.000	EA	1,994.50	3,000.00	3,100.59
0780	603-CB007	42" Reinforced Concrete End Section	2.000	EA	4,138.00	4,100.00	8,377.38

Add 2 Lanes to I-55 from SR 463 to Gluckstadt Road, & Mill & Overlay approximately 0.77 miles on I-55 from Gluckstadt Road north, known as Federal Aid Project Nos. STP-0055-02(271) / 108168301 & STP-0055-02(275) / 108168302 in Madison County.					T. L. Wallace Construction, Inc.	W. G. Yates & Sons Construction Company	Necaise Brothers Construction Co., Inc.
		MISSISSIPPI DEPARTMENT OF TRANSPORTATION: $179,163,056.40			$187,725,441.40	$193,158,658.00	$202,217,715.43
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
0790	603-CE008	29" x 18" Concrete Arch Pipe, Class A III	104.000	LF	141.90	160.00	149.96
0800	603-CE018	44" x 27" Concrete Arch Pipe, Class A III	88.000	LF	194.95	225.00	318.92
0810	603-CE034	65" x 40" Concrete Arch Pipe, Class A III	40.000	LF	327.90	450.00	466.99
0820	603-CF003	29" x 18" Concrete Arch Pipe End Section	2.000	EA	2,008.50	2,000.00	1,927.26
0830	603-CF005	44" x 27" Concrete Arch Pipe End Section	2.000	EA	3,728.25	3,100.00	3,100.60
0840	603-CF008	65" x 40" Concrete Arch Pipe End Section	2.000	EA	6,272.00	5,250.00	9,552.25
0850	603-SB012	18" Branch Connections, Stub into Box Culvert	4.000	EA	3,256.75	5,000.00	9,245.74
0860	603-SB028	24" Branch Connections, Stub into Box Culvert	2.000	EA	3,923.75	10,000.00	10,420.62
0870	604-A001	Castings	79.000	LBS	6.55	15.00	5.87
0880	604-B001	Gratings	10,897.000	LBS	6.00	10.00	5.87
0890	605-AA001	Geotextile for Subsurface Drainage, Type III	424.000	SY	2.45	6.00	5.33
0900	605-O002	4" Perforated Sewer Pipe for Underdrains, SDR 23.5	762.000	LF	22.45	50.00	28.38
0910	605-P002	4" Non-perforated Sewer Pipe for Underdrains, SDR 23.5	190.000	LF	26.80	50.00	28.39
0920	605-W001	Filter Material for Combination Storm Drain and/or Underdrains,Type A, FM	29.000	CY	111.45	250.00	175.02
0930	606-B001	Guard Rail, Class A, Type 1	550.000	LF	32.30	30.00	34.66
0940	606-B006	Guard Rail, Class A, Type 1, Double Faced	313.000	LF	52.50	51.00	56.39
0950	606-C003	Guard Rail, Cable Anchor, Type 1	1.000	EA	2,048.75	2,050.00	2,291.00
0960	606-D022	Guard Rail, Bridge End Section, Type I	4.000	EA	4,101.25	3,950.00	4,405.78
0970	606-E001	Guard Rail, Terminal End Section	5.000	EA	4,210.75	4,050.00	4,523.26
0980	607-B018	60" Type I Chain Link Fence, Class II	40,947.000	LF	13.25	12.75	15.27
0990	607-E001	Barbed Wire Fence, Single Strand	600.000	LF	0.65	0.70	3.52
1000	607-G127	Gate, 3' x 60" Chain Link	12.000	EA	854.75	825.00	2,702.21
1010	607-P1003	Line Post, 14' x 2 1/2" Galvanized Steel	8.000	EA	147.20	150.00	281.97
1020	607-P1008	Line Post, 7' x 1 1/2" Galvanized Steel	3,834.000	EA	78.85	75.00	135.11
1030	607-P2004	Brace Post, 7 1/2' x 2" Galvanized Steel	247.000	EA	287.55	280.00	152.73
1040	607-P2022	Brace Post, 5' x 2 1/2" Galvanized Steel	8.000	EA	280.50	280.00	129.24

Add 2 Lanes to I-55 from SR 463 to Gluckstadt Road, & Mill & Overlay approximately 0.77 miles on I-55 from Gluckstadt Road north, known as Federal Aid Project Nos. STP-0055-02(271) / 108168301 & STP-0055-02(275) / 108168302 in Madison County.					T. L. Wallace Construction, Inc.	W. G. Yates & Sons Construction Company	Necaise Brothers Construction Co., Inc.
		MISSISSIPPI DEPARTMENT OF TRANSPORTATION: $179,163,056.40			$187,725,441.40	$193,158,658.00	$202,217,715.43
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
1050	607-P3004	Gate Post, 8' x 2 1/2" Galvanized Steel	24.000	EA	298.60	300.00	176.23
1060	608-A001	Concrete Sidewalk, Without Reinforcement	870.000	SY	93.00	86.00	105.74
1070	609-C001	Concrete Integral Curb, Type 1	173.000	LF	43.10	41.00	51.70
1080	609-D004	Combination Concrete Curb and Gutter Type 2 Modified	1,785.000	LF	44.85	41.00	52.58
1090	609-D007	Combination Concrete Curb and Gutter Type 3 Modified	3,101.000	LF	44.85	41.00	52.58
1100	612-B001	Flowable Fill, Non-Excavatable	22.000	CY	434.85	450.00	113.47
1110	615-A004	Concrete Bridge End Barrier, 43.5"	287.000	LF	206.60	230.00	217.35
1120	615-A007	Concrete Pier Protection Barrier, 54"	256.000	LF	869.80	835.00	916.40
1130	615-A023	Concrete Type IV Modified, 42" Height, Cast-in-Place Median Barrier	34,372.000	LF	334.85	340.00	350.11
1140	616-A001	Concrete Median and/or Island Pavement, 10-inch	130.000	SY	229.70	255.00	270.23
1150	616-A004	Concrete Median and/or Island Pavement, 4-inch	611.000	SY	73.85	110.00	96.94
1160	616-B001	Bituminous Median and/or Island Pavement	776.000	SY	54.60	105.00	93.99
1170	617-A001	Right-of-Way Marker	3.000	EA	525.30	1,050.00	352.46
1180	619-A1001	Temporary Traffic Stripe, Continuous White	84.000	MI	2,734.25	1,500.00	1,762.31
1190	619-A2001	Temporary Traffic Stripe, Continuous Yellow	81.000	MI	2,734.25	1,500.00	1,762.31
1200	619-A3001	Temporary Traffic Stripe, Skip White	96.000	MI	2,734.25	1,500.00	1,762.31
1210	619-A5001	Temporary Traffic Stripe, Detail	142,991.000	LF	0.55	0.30	0.35
1220	619-A6001	Temporary Traffic Stripe, Legend	3,431.000	SF	3.30	1.00	1.17
1230	619-A6002	Temporary Traffic Stripe, Legend	2,568.000	LF	2.10	1.00	1.17
1240	619-C6001	Red-Clear Reflective High Performance Raised Marker	20,347.000	EA	19.70	5.00	5.87
1250	619-C8001	One-Way Clear Reflective High Performance Raised Marker	2,075.000	EA	19.70	15.00	17.62
1260	619-C9001	One-Way Yellow Reflective High Performance Raised Marker	2,099.000	EA	19.70	15.00	17.62
1270	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	95.000	SF	12.95	13.00	14.10
1280	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	2,060.000	SF	13.50	13.00	14.10
1290	619-F1001	Concrete Median Barrier, Precast	9,920.000	LF	48.65	65.00	80.00
1300	619-F2001	Remove and Reset Concrete Median Barrier, Precast	85,000.000	LF	19.85	17.50	17.00

Add 2 Lanes to I-55 from SR 463 to Gluckstadt Road, & Mill & Overlay approximately 0.77 miles on I-55 from Gluckstadt Road north, known as Federal Aid Project Nos. STP-0055-02(271) / 108168301 & STP-0055-02(275) / 108168302 in Madison County.					T. L. Wallace Construction, Inc.	W. G. Yates & Sons Construction Company	Necaise Brothers Construction Co., Inc.
		MISSISSIPPI DEPARTMENT OF TRANSPORTATION: $179,163,056.40			$187,725,441.40	$193,158,658.00	$202,217,715.43
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
1310	619-G4005	Barricades, Type III, Single Faced	228.000	LF	32.35	32.00	35.25
1320	619-G5001	Free Standing Plastic Drums	1,151.000	EA	67.30	63.00	70.49
1330	619-G7001	Warning Lights, Type "B"	22.000	EA	134.65	135.00	146.86
1340	619-J1004	Impact Attenuator, 60 MPH	6.000	EA	19,280.00	7,800.00	8,811.55
1350	619-J2004	Impact Attenuator, 60 MPH, Replacement Package	6.000	EA	19,930.00	4,700.00	5,286.93
1360	619-J3001	Remove and Reset Impact Attenuator	20.000	EA	2,802.50	2,700.00	2,937.18
1370	620-A001	Mobilization	1.000	LS	21,870,000.00	19,300,000.00	24,000,000.00
1380	622-A004	Engineer's Field Office Building, Type 3	1.000	EA	277,000.00	500,000.00	110,000.00
1390	629-A005	Vehicular Impact Attenuator, 70 MPH	1.000	EA	190,000.00	57,500.00	65,792.93
1400	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	178.000	SF	22.10	22.00	24.67
1410	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	469.000	SF	24.10	23.00	25.85
1420	630-A005	Standard Roadside Signs, Sheet Aluminum, 0.1" Thickness	349.000	SF	22.60	23.00	25.26
1430	630-B002	Interstate Directional Signs, Bolted Extruded Aluminum Panels, Ground Mounted	378.000	SF	33.90	33.00	36.42
1440	630-B003	Interstate Directional Signs, Bolted Extruded Aluminum Panels, Overhead Mounted	7,776.000	SF	35.00	34.00	37.60
1450	630-C001	Square Tube Posts, 4.0 lb/ft	559.000	LF	56.90	55.00	61.09
1460	630-C004	Square Tube Posts, 9.0 lb/ft	136.000	LF	93.00	90.00	99.86
1470	630-C005	Square Tube Posts, 2.0 lb/ft	944.000	LF	20.80	20.00	22.32
1480	630-C1001	Square Post Inner Sleeve	64.000	LF	20.00	20.00	22.32
1490	630-D006	Structural Steel Beams, W6 x 12	51.000	LF	89.30	90.00	99.86
1500	630-D008	Structural Steel Beams, W6 x 9	136.000	LF	93.00	90.00	99.86
1510	630-E001	Structural Steel Angles & Bars, 3 1/2" x 3 1/2" x 1/4" Angles	63.000	LBS	5.25	5.25	5.87
1520	630-E002	Structural Steel Angles & Bars, 3" x 3" x 1/4" Angles	132.000	LBS	5.25	5.25	5.87
1530	630-F006	Delineators, Guard Rail, White	28.000	EA	37.85	37.75	42.30
1540	630-F007	Delineators, Guard Rail, Yellow	10.000	EA	37.85	37.75	42.30
1550	630-F010	Delineators, Post Mounted, Double White	152.000	EA	136.70	130.00	146.86
1560	630-F011	Delineators, Post Mounted, Double Yellow	54.000	EA	131.35	130.00	146.86

Add 2 Lanes to I-55 from SR 463 to Gluckstadt Road, & Mill & Overlay approximately 0.77 miles on I-55 from Gluckstadt Road north, known as Federal Aid Project Nos. STP-0055-02(271) / 108168301 & STP-0055-02(275) / 108168302 in Madison County.					T. L. Wallace Construction, Inc.	W. G. Yates & Sons Construction Company	Necaise Brothers Construction Co., Inc.
		MISSISSIPPI DEPARTMENT OF TRANSPORTATION: $179,163,056.40			$187,725,441.40	$193,158,658.00	$202,217,715.43
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
1570	630-F012	Delineators, Post Mounted, Single White	61.000	EA	120.85	120.00	135.11
1580	630-F013	Delineators, Post Mounted, Single Yellow	14.000	EA	120.85	120.00	135.11
1590	630-G004	Type 3 Object Markers, OM-3R or OM-3L	4.000	EA	162.85	160.00	182.11
1600	630-I003	Metal Overhead Sign Supports, Assembly No. 1, Contractor Designed	1.000	LS	225,000.00	215,000.00	240,849.11
1610	630-I004	Metal Overhead Sign Supports, Assembly No. 10, Contractor Designed	1.000	LS	225,000.00	215,000.00	240,849.11
1620	630-I005	Metal Overhead Sign Supports, Assembly No. 11, Contractor Designed	1.000	LS	225,000.00	215,000.00	240,849.11
1630	630-I006	Metal Overhead Sign Supports, Assembly No. 12, Contractor Designed	1.000	LS	225,000.00	215,000.00	240,849.11
1640	630-I007	Metal Overhead Sign Supports, Assembly No. 13, Contractor Designed	1.000	LS	225,000.00	215,000.00	240,849.11
1650	630-I008	Metal Overhead Sign Supports, Assembly No. 14, Contractor Designed	1.000	LS	225,000.00	215,000.00	240,849.11
1660	630-I009	Metal Overhead Sign Supports, Assembly No. 15, Contractor Designed	1.000	LS	225,000.00	215,000.00	240,849.11
1670	630-I010	Metal Overhead Sign Supports, Assembly No. 16, Contractor Designed	1.000	LS	288,000.00	255,000.00	524,381.37
1680	630-I015	Metal Overhead Sign Supports, Assembly No. 2, Contractor Designed	1.000	LS	225,000.00	215,000.00	240,849.11
1690	630-I020	Metal Overhead Sign Supports, Assembly No. 3, Contractor Designed	1.000	LS	225,000.00	215,000.00	240,849.11
1700	630-I022	Metal Overhead Sign Supports, Assembly No. 4, Contractor Designed	1.000	LS	225,000.00	215,000.00	240,849.11
1710	630-I024	Metal Overhead Sign Supports, Assembly No. 5, Contractor Designed	1.000	LS	225,000.00	215,000.00	240,849.11
1720	630-I025	Metal Overhead Sign Supports, Assembly No. 6, Contractor Designed	1.000	LS	225,000.00	215,000.00	240,849.11
1730	630-I026	Metal Overhead Sign Supports, Assembly No. 7, Contractor Designed	1.000	LS	225,000.00	215,000.00	240,849.11
1740	630-I027	Metal Overhead Sign Supports, Assembly No. 8, Contractor Designed	1.000	LS	225,000.00	215,000.00	240,849.11
1750	630-I028	Metal Overhead Sign Supports, Assembly No. 9, Contractor Designed	1.000	LS	225,000.00	215,000.00	240,849.11
1760	635-A059	Traffic Signal Head, Type 1	12.000	EA	1,137.50	1,125.00	1,245.37
1770	635-A065	Traffic Signal Head, Type 2 FYA	2.000	EA	2,153.75	2,250.00	2,496.61
1780	635-A070	Traffic Signal Head, Type 3	2.000	EA	1,870.25	2,250.00	2,496.61
1790	635-A073	Traffic Signal Head, Type 4	1.000	EA	1,092.75	1,125.00	1,245.36
1800	635-A076	Traffic Signal Head, Type 6	2.000	EA	893.05	1,125.00	1,245.37
1810	647-A001	Removal of Existing Traffic Signal Equipment	1.000	LS	7,328.00	3,350.00	3,747.84
1820	682-A005	Underground Branch Circuit, AWG 1/0, 3 Conductor	4,378.000	LF	27.90	26.00	29.49

Add 2 Lanes to I-55 from SR 463 to Gluckstadt Road, & Mill & Overlay approximately 0.77 miles on I-55 from Gluckstadt Road north, known as Federal Aid Project Nos. STP-0055-02(271) / 108168301 & STP-0055-02(275) / 108168302 in Madison County.					T. L. Wallace Construction, Inc.	W. G. Yates & Sons Construction Company	Necaise Brothers Construction Co., Inc.
				MISSISSIPPI DEPARTMENT OF TRANSPORTATION: $179,163,056.40	$187,725,441.40	$193,158,658.00	$202,217,715.43
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
1830	682-A007	Underground Branch Circuit, AWG 1/0, 5 Conductor	2,642.000	LF	42.40	38.00	43.53
1840	682-A018	Underground Branch Circuit, AWG 2, 3 Conductor	8,904.000	LF	21.90	21.00	23.50
1850	682-A034	Underground Branch Circuit, AWG 6, 3 Conductor	3,180.000	LF	13.70	13.50	15.04
1860	682-A039	Underground Branch Circuit, AWG 8, 3 Conductor	1,680.000	LF	12.60	11.00	12.28
1870	682-B005	Underground Branch Circuit, Jacked or Bored, AWG 1/0, 3 Conductor	90.000	LF	52.55	37.00	41.53
1880	682-B007	Underground Branch Circuit, Jacked or Bored, AWG 1/0, 5 Conductor	90.000	LF	63.05	50.00	55.51
1890	682-B016	Underground Branch Circuit, Jacked or Bored, AWG 2, 3 Conductor	620.000	LF	36.10	29.00	32.07
1900	682-B025	Underground Branch Circuit, Jacked or Bored, AWG 4, 3 Conductor	870.000	LF	30.65	27.00	30.31
1910	682-B032	Underground Branch Circuit, Jacked or Bored, AWG 6, 3 Conductor	490.000	LF	21.60	25.00	27.08
1920	682-B037	Underground Branch Circuit, Jacked or Bored, AWG 8, 3 Conductor	340.000	LF	19.20	23.00	24.67
1930	682-C006	Structure Mounted Branch Circuit, AWG 1/0, 5 Conductor	200.000	LF	103.90	86.00	95.34
1940	682-C009	Structure Mounted Branch Circuit, AWG 10, 3 Conductor	480.000	LF	54.70	37.00	40.42
1950	682-C015	Structure Mounted Branch Circuit, AWG 2, 3 Conductor	150.000	LF	87.50	67.00	74.25
1960	682-D002	Structure Mounted Pull Box	10.000	EA	2,050.75	1,750.00	1,962.04
1970	682-D003	Underground Pull Box	38.000	EA	1,066.50	2,000.00	2,214.64
1980	682-E001	Structure Mounted Junction Box	3.000	EA	1,970.00	1,500.00	1,680.07
1990	682-E003	Underground Junction Box With Concrete Pad	21.000	EA	2,182.00	3,150.00	3,530.50
2000	682-F002	Secondary Power Controllers	3.000	EA	43,730.00	42,250.00	47,306.29
2010	683-A002	Lighting Assembly, High Mast, LED, Type 120-4-A	32.000	EA	50,940.00	49,250.00	55,130.95
2020	683-A124	Lighting Assembly, High Mast, LED, Type 120-8-S	4.000	EA	58,310.00	56,800.00	63,654.66
2030	683-A137	Lighting Assembly, High Mast, LED, Type 120-8-A	1.000	EA	57,830.00	58,100.00	65,105.63
2040	683-A138	Lighting Assembly, High Mast, LED, Type 120-6-A	1.000	EA	60,980.00	53,000.00	59,307.62
2050	683-B212	Lighting Assembly, Low Mast, LED, Type 40-1-8-110	11.000	EA	6,070.00	5,300.00	5,891.99
2060	683-B213	Lighting Assembly, Low Mast, LED, Type 40-2-8-110	1.000	EA	7,617.00	7,100.00	7,942.15
2070	683-C010	Lighting Assembly, Underpass, Type UP	8.000	EA	1,339.75	1,275.00	1,415.72
2080	683-D001	Portable Electric Power Units	1.000	EA	5,778.50	4,550.00	5,104.83

Add 2 Lanes to I-55 from SR 463 to Gluckstadt Road, & Mill & Overlay approximately 0.77 miles on I-55 from Gluckstadt Road north, known as Federal Aid Project Nos. STP-0055-02(271) / 108168301 & STP-0055-02(275) / 108168302 in Madison County.					T. L. Wallace Construction, Inc.	W. G. Yates & Sons Construction Company	Necaise Brothers Construction Co., Inc.
		MISSISSIPPI DEPARTMENT OF TRANSPORTATION: $179,163,056.40			$187,725,441.40	$193,158,658.00	$202,217,715.43
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
2090	684-A003	Pole Foundation, 24" Diameter	12.000	CY	1,698.25	2,350.00	2,608.22
2100	684-A006	Pole Foundation, 42" Diameter	271.000	CY	2,680.50	2,200.00	2,461.36
2110	684-B003	Slip Casing, 24" Diameter	8.000	LF	52.55	105.00	117.49
2120	684-B006	Slip Casing, 42" Diameter	20.000	LF	105.10	525.00	587.44
2130	699-A001	Roadway Construction Stakes	1.000	LS	1,674,000.00	2,500,000.00	1,900,000.00
2140	815-A002	Loose Riprap, Size 100	1,250.000	TON	121.70	125.00	125.00
2150	815-A007	Loose Riprap, Size 300	7,050.000	TON	121.70	125.00	125.00
2160	815-E001	Geotextile under Riprap	8,681.000	SY	2.70	5.00	6.00
2170	815-F002	Sediment Control Stone	3,000.000	TON	109.95	150.00	150.00
2180	907-234-A001	Temporary Silt Fence	17,000.000	LF	4.40	6.00	4.70
2190	907-234-C001	Super Silt Fence	2,575.000	LF	16.40	19.00	17.62
2200	907-234-D001	Inlet Siltation Guard	15.000	EA	656.20	625.00	704.92
2210	907-234-E001	Reset Inlet Siltation Guard	15.000	EA	315.20	325.00	352.46
2220	907-248-A001	Temporary Site Drainage	1.000	LS	1,508,000.00	300,000.00	800,000.00
2230	907-253-A001	Coir Fiber Baffle	1,021.000	LF	16.40	15.50	17.62
2240	907-402-A002	Open Graded Friction Course, 9.5-mm Mixture	11,193.000	TON	193.65	220.00	206.78
2250	907-402-B001	Bituminous Tack Coat	39,202.000	GAL	4.40	4.50	4.66
2260	907-403-A001	12.5-mm, HT, Asphalt Pavement	29,040.000	TON	148.30	160.00	158.37
2270	907-403-A004	19-mm, HT, Asphalt Pavement	35,680.000	TON	143.75	144.00	153.50
2280	907-403-A006	19-mm, ST, Asphalt Pavement	35,456.000	TON	140.20	137.00	149.68
2290	907-403-A013	9.5-mm, HT, Asphalt Pavement	4,667.000	TON	186.20	175.00	178.23
2300	907-403-A015	9.5-mm, ST, Asphalt Pavement	608.000	TON	202.45	194.00	216.18
2310	907-403-B001	12.5-mm, HT, Asphalt Pavement, Leveling	42,798.000	TON	167.45	150.00	178.82
2320	907-403-B010	9.5-mm, HT, Asphalt Pavement, Leveling	5,921.000	TON	179.55	172.00	191.74
2330	907-403-S001	Joint Sealant	34.000	MI	1,799.00	3,500.00	1,920.92
2340	907-405-A001	Stone Matrix Asphalt, 9.5 mm Mixture	44,502.000	TON	194.20	195.00	207.37

Add 2 Lanes to I-55 from SR 463 to Gluckstadt Road, & Mill & Overlay approximately 0.77 miles on I-55 from Gluckstadt Road north, known as Federal Aid Project Nos. STP-0055-02(271) / 108168301 & STP-0055-02(275) / 108168302 in Madison County.					T. L. Wallace Construction, Inc.	W. G. Yates & Sons Construction Company	Necaise Brothers Construction Co., Inc.
		MISSISSIPPI DEPARTMENT OF TRANSPORTATION: $179,163,056.40			$187,725,441.40	$193,158,658.00	$202,217,715.43
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
2350	907-405-A002	Stone Matrix Asphalt, 12.5 mm Mixture	20,101.000	TON	199.55	195.00	213.06
2360	907-407-A001	Asphalt for Tack Coat	143,298.000	GAL	4.45	4.50	4.72
2370	907-413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	576.000	LF	16.40	10.25	11.75
2380	907-501-F001	Concrete Lug Anchors	640.000	LF	767.00	710.00	822.41
2390	907-502-A001	Reinforced Cement Concrete Bridge End Pavement	1,693.000	SY	328.10	305.00	352.46
2400	907-601-A001	Class "B" Structural Concrete	302.000	CY	2,403.25	2,750.00	2,800.00
2410	907-601-B001	Class "B" Structural Concrete, Minor Structures	88.000	CY	3,173.75	6,100.00	4,327.16
2420	907-608-C001	Detectable Warning Panels	120.000	SF	36.80	36.00	41.12
2430	907-618-A001	Maintenance of Traffic	1.000	LS	4,952,730.00	7,550,000.00	9,000,000.00
2440	907-618-M1001	Service Patrol	1.000	LS	2,338,845.00	4,000,000.00	4,000,000.00
2450	907-618-M2001	Work Zone Law Enforcement	7,114.000	HRS	60.00	60.00	60.00
2460	907-619-E3001	Changeable Message Sign	2.000	EA	17,830.00	17,100.00	18,686.37
2470	907-619-M1002	Smart Work Zone, Portable Queue Trailer	24.000	EA	8,725.75	8,375.00	9,144.92
2480	907-619-M1003	Smart Work Zone, Portable Camera Trailer	10.000	EA	29,130.00	28,000.00	30,523.81
2490	907-619-M1004	Smart Work Zone, Portable Message Board Trailer	12.000	EA	18,190.00	17,450.00	19,064.21
2500	907-619-M2001	Smart Work Zone, Portable Queue Trailer, Operational Month	84.000	EA	405.85	375.00	425.30
2510	907-619-M2002	Smart Work Zone, Portable Camera Trailer, Operational Month	84.000	EA	578.45	535.00	606.23
2520	907-619-M2003	Smart Work Zone, Portable Message Board Trailer, Operational Month	84.000	EA	405.85	375.00	425.30
2530	907-619-M2004	Smart Work Zone, Portable Bluetooth Detection System, Additional Device, Operational Month	84.000	EA	405.85	375.00	425.30
2540	907-619-M3002	Smart Work Zone, System Monitoring, Operational Month	84.000	EA	560.50	520.00	587.44
2550	907-626-A010	6" Thermoplastic Traffic Stripe, Skip White	21.000	MI	7,655.75	8,600.00	9,986.43
2560	907-626-B006	6" Thermoplastic Traffic Stripe, Continuous White	14.000	MI	10,390.00	12,350.00	14,333.46
2570	907-626-E005	6" Thermoplastic Traffic Stripe, Continuous Yellow	13.000	MI	10,290.00	12,050.00	13,981.00
2580	907-626-G004	Thermoplastic Detail Stripe, White	37,665.000	LF	7.15	4.05	4.70
2590	907-626-G005	Thermoplastic Detail Stripe, Yellow	1,966.000	LF	7.70	4.05	4.70
2600	907-626-H009	Thermoplastic Legend, White	1,096.000	SF	26.25	30.50	35.25

Add 2 Lanes to I-55 from SR 463 to Gluckstadt Road, & Mill & Overlay approximately 0.77 miles on I-55 from Gluckstadt Road north, known as Federal Aid Project Nos. STP-0055-02(271) / 108168301 & STP-0055-02(275) / 108168302 in Madison County.					T. L. Wallace Construction, Inc.	W. G. Yates & Sons Construction Company	Necaise Brothers Construction Co., Inc.
		MISSISSIPPI DEPARTMENT OF TRANSPORTATION: $179,163,056.40			$187,725,441.40	$193,158,658.00	$202,217,715.43
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
2610	907-626-H010	Thermoplastic Legend, White	1,284.000	LF	13.15	15.25	17.62
2620	907-627-K001	Red-Clear Reflective High Performance Raised Markers	6,145.000	EA	19.70	15.75	17.62
2622	907-627-L001	Two-Way Yellow Reflective High Performance Raised Markers	1,192.000	EA	19.70	15.75	17.62
2630	907-632-A007	Solid State Traffic Cabinet Assembly, Type III Cabinet, Type 1 Controller	2.000	EA	26,060.00	25,750.00	28,702.17
2640	907-632-D001	Solid State Traffic Actuated Controller, Type 1	2.000	EA	6,042.50	5,575.00	6,238.58
2650	907-632-G001	Malfunction Management Unit	2.000	EA	1,970.00	2,250.00	2,496.61
2660	907-632-J001	Power Service Pedestal	6.000	EA	31,700.00	31,000.00	34,827.17
2670	907-634-A047	Traffic Signal Equipment Pole, Type II(L), 30' Shaft, 55' Arm	1.000	EA	30,240.00	33,500.00	37,431.47
2680	907-634-A083	Traffic Signal Equipment Pole, Type II, 17' Shaft, 45' Arm	1.000	EA	20,510.00	31,250.00	34,940.75
2690	907-634-A374	Traffic Signal Equipment Pole, Type III, 17' Shaft, 35' & 40' Arms	1.000	EA	24,340.00	35,750.00	39,928.09
2700	907-634-A397	Traffic Signal Equipment Pole, Type III, 17' Shaft, 50' & 50' Arms	1.000	EA	29,400.00	44,550.00	49,914.52
2710	907-634-A545	Traffic Signal Equipment Pole, Type VI, 8' Shaft	1.000	EA	2,075.00	1,125.00	1,251.25
2720	907-634-C001	Pole Foundations, Class "B" Concrete	16.000	CY	1,148.50	1,125.00	1,251.24
2730	907-634-E001	Camera Pole with Foundation, 50' Pole	4.000	EA	19,270.00	20,000.00	22,181.62
2740	907-636-B003	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 10, 2 Conductor	190.000	LF	3.15	3.40	3.76
2750	907-636-B014	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 14, 5 Conductor	425.000	LF	3.00	3.40	3.76
2760	907-636-B016	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 14, 8 Conductor	915.000	LF	3.95	3.40	3.76
2770	907-636-B025	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 6, 3 Conductor	225.000	LF	9.75	6.75	7.52
2780	907-636-B043	Electric Cable, Underground in Conduit, THHN, AWG #2, 4 Conductor	40.000	LF	24.20	18.00	19.97
2790	907-636-B053	Electric Cable, Underground in Conduit, THHN, AWG #6, 3 Conductor	1,120.000	LF	7.35	6.50	7.28
2800	907-636-D001	Electric Cable, Aerial Supported in Conduit, IMSA 20-1, AWG 10, 2 Conductor	40.000	LF	4.20	3.40	3.76
2810	907-636-D006	Electric Cable, Aerial Supported in Conduit, IMSA 20-1, AWG 14, 5 Conductor	20.000	LF	4.20	3.40	3.76
2820	907-636-D008	Electric Cable, Aerial Supported in Conduit, IMSA 20-1, AWG 14, 8 Conductor	380.000	LF	5.25	3.40	3.76
2830	907-636-D022	Electric Cable, Aerial Supported in Conduit, IMSA 20-1, AWG 6, 3 Conductor	40.000	LF	10.55	6.75	7.52
2840	907-637-A002	Pullbox Enclosure, Type 2	17.000	EA	1,121.00	1,425.00	1,591.95
2850	907-637-A003	Pullbox Enclosure, Type 3	2.000	EA	1,381.75	2,025.00	2,249.89

Add 2 Lanes to I-55 from SR 463 to Gluckstadt Road, & Mill & Overlay approximately 0.77 miles on I-55 from Gluckstadt Road north, known as Federal Aid Project Nos. STP-0055-02(271) / 108168301 & STP-0055-02(275) / 108168302 in Madison County.					T. L. Wallace Construction, Inc.	W. G. Yates & Sons Construction Company	Necaise Brothers Construction Co., Inc.
		MISSISSIPPI DEPARTMENT OF TRANSPORTATION: $179,163,056.40			$187,725,441.40	$193,158,658.00	$202,217,715.43
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
2860	907-637-A004	Pullbox Enclosure, Type 4	16.000	EA	1,799.25	1,900.00	2,126.52
2870	907-637-A005	Pullbox Enclosure, Type 5	11.000	EA	2,258.50	2,600.00	2,931.31
2880	907-637-C028	Traffic Signal Conduit, Underground, Type 4, 2"	160.000	LF	12.65	17.00	18.74
2890	907-637-C030	Traffic Signal Conduit, Underground, Type 4, 3"	105.000	LF	15.80	22.50	24.97
2900	907-637-D003	Traffic Signal Conduit, Underground Drilled or Jacked, Rolled Pipe, 3"	670.000	LF	20.25	22.50	24.97
2910	907-637-H001	Traffic Signal Conduit Bank, Underground, Rolled Pipe, 2 @ 2"	160.000	LF	10.00	22.00	24.61
2920	907-637-H002	Traffic Signal Conduit Bank, Underground, Rolled Pipe, 2"	445.000	LF	9.50	17.00	18.74
2930	907-637-I001	Traffic Signal Conduit Bank, Underground, Drilled or Jacked, Rolled Pipe, 2 @ 2"	23,495.000	LF	10.40	12.00	13.16
2940	907-637-I002	Traffic Signal Conduit Bank, Underground, Drilled or Jacked, Rolled Pipe, 2"	760.000	LF	10.00	21.00	23.32
2950	907-640-B001	Shielded Cable, AWG #14, 2 Conductor	440.000	LF	2.10	2.25	2.53
2960	907-641-A002	Signal Stop Bar Radar Vehicle Detection Sensor, Type 2	6.000	EA	8,011.25	9,000.00	9,986.43
2970	907-641-B002	Signal Advanced Radar Vehicle Detection Sensor, Type 2	8.000	EA	8,536.00	9,000.00	9,986.43
2980	907-641-C002	ITS Radar Vehicle Detection Sensor	2.000	EA	7,847.00	8,500.00	9,369.62
2990	907-641-D001	Radar Vehicle Detection Cable	2,505.000	LF	4.65	4.50	4.99
3000	907-641-F002	Signal Radar Vehicle Detection Processor, Type 2	4.000	EA	6,720.75	6,700.00	7,489.82
3010	907-641-G002	ITS Radar Vehicle Detection Processor, Type 2	2.000	EA	1,602.25	525.00	587.44
3020	907-645-B001	Accessible Pedestrian Detection Assembly	2.000	EA	1,008.75	1,675.00	1,873.92
3030	907-650-A002	On Street Video Equipment, Fixed Type	12.000	EA	3,002.25	3,150.00	3,518.75
3040	907-650-A003	On Street Video Equipment, PTZ Type	6.000	EA	4,320.00	4,600.00	5,157.70
3050	907-650-A004	On Street Video Equipment, PTZ Type, Signal Monitoring	5.000	EA	3,182.75	2,800.00	3,119.29
3060	907-653-A001	Traffic Sign	27.000	SF	105.10	90.00	99.86
3070	907-656-A001	Dynamic Message Sign, Type 1	1.000	EA	130,000.00	130,500.00	146,271.78
3080	907-659-A001	Traffic Management Center Modifications	1.000	LS	174,000.00	73,000.00	81,735.96
3090	907-660-A002	Equipment Cabinet, Type B	5.000	EA	7,650.25	6,500.00	7,172.61
3100	907-660-A003	Equipment Cabinet, Type C	1.000	EA	15,180.00	14,300.00	16,007.66
3110	907-661-A004	Fiber Optic Cable, 72 SM	20,470.000	LF	3.55	3.30	3.70

Add 2 Lanes to I-55 from SR 463 to Gluckstadt Road, & Mill & Overlay approximately 0.77 miles on I-55 from Gluckstadt Road north, known as Federal Aid Project Nos. STP-0055-02(271) / 108168301 & STP-0055-02(275) / 108168302 in Madison County.					T. L. Wallace Construction, Inc.	W. G. Yates & Sons Construction Company	Necaise Brothers Construction Co., Inc.
		MISSISSIPPI DEPARTMENT OF TRANSPORTATION: $179,163,056.40			$187,725,441.40	$193,158,658.00	$202,217,715.43
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
3120	907-661-B002	Fiber Optic Drop Cable, 12 SM	3,805.000	LF	3.30	4.00	4.41
3130	907-663-A001	Network Switch, Type A	10.000	EA	1,569.50	1,775.00	1,985.54
3140	907-663-A002	Network Switch, Type B	1.000	EA	1,912.25	2,360.00	2,643.47
3150	907-663-A003	Network Switch, Type C	1.000	EA	140,000.00	145,000.00	162,226.55
3160	907-663-A005	Network Switch, Type E	2.000	EA	40,680.00	40,700.00	45,596.85
3170	907-666-A001	Bluetooth Detection System, Type A	3.000	EA	24,560.00	10,800.00	11,812.18
3180	907-682-A1011	Branch Circuit Wire, AWG #2, 3 Conductor	440.000	LF	18.65	13.50	15.21
3190	907-682-A1019	Branch Circuit Wire, AWG #4, 3 Conductor	830.000	LF	10.25	9.00	10.28
3200	907-906001	Trainees	1,040.000	HRS	5.00	5.00	5.00
3210	304-F001	3/4" and Down Crushed Stone Base	117,600.000	TON			
3220	304-F002	Size 610 Crushed Stone Base	117,600.000	TON	86.25	100.00	95.00
3230	304-F003	Size 825B Crushed Stone Base	117,600.000	TON			
3240	605-W002	Filter Material for Combination Storm Drain and/or Underdrains,Type B, FM	800.000	CY	77.75	175.00	150.00
3250	605-W003	Filter Material for Combination Storm Drain and/or Underdrains,Type C, FM	800.000	CY			
3260	501-K001	Transverse Grooving	5,588.000	SY	3.05	3.00	3.23
3270	605-AA001	Geotextile for Subsurface Drainage, Type III	2,476.000	SY	2.45	6.00	6.00
3280	605-T002	6" Perforated Pipe for Underdrains	3,262.000	LF	33.30	60.00	30.00
3290	605-X002	Filter Material for Filter Beds, Type A	258.000	CY	114.95	300.00	150.00
3300	605-X003	Filter Material for Filter Beds, Type B	613.000	CY	77.80	175.00	150.00
3310	605-Y002	Impervious Material, Type D	1,059.000	CY	138.45	55.00	75.00
3320	803-C002	14" x 14" Prestressed Concrete Piling	8,295.000	LF	82.75	100.00	95.93
3330	803-D002	HP 12 x 53 Steel Piling	4,816.000	LF	87.65	45.00	105.01
3340	803-D006	HP 14 x 73 Steel Piling	7,608.000	LF	117.20	45.00	131.06
3350	803-D007	HP 14 x 89 Steel Piling	17,688.000	LF	138.70	35.00	153.39
3360	803-P015	24" Steel Pipe Piling, Wall Thickness 0.625"	5,425.000	LF	297.15	110.00	337.39
3370	804-C188	80' Prestressed Concrete Beam, Type FIB-36	1,272.000	LF	352.55	450.00	567.46

Add 2 Lines to I-55 from SR 463 to Gluckstadt Road, & Mill & Overlay approximately 0.77 miles on I-55 from Gluckstadt Road north, known as Federal Aid Project Nos. STP-0055-02(271) / 108168301 & STP-0055-02(275) / 108168302 in Madison County.					T. L. Wallace Construction, Inc.	W. G. Yates & Sons Construction Company	Necaise Brothers Construction Co., Inc.
		MISSISSIPPI DEPARTMENT OF TRANSPORTATION: $179,163,056.40			$187,725,441.40	$193,158,658.00	$202,217,715.43
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
3380	804-C195	85' Prestressed Concrete Beam, Type FIB-36	1,352.000	LF	350.40	450.00	558.01
3390	804-C208	60' Prestressed Concrete Beam, Type FIB-36	1,904.000	LF	352.00	450.00	558.01
3400	804-C274	40' Prestressed Concrete Beam, Type FIB-36	1,264.000	LF	344.60	450.00	574.22
3410	805-A001	Reinforcement	1,081,334.000	LBS	2.10	2.60	2.07
3420	805-C001	Reinforcement, Corrosion Resistant	22,208.000	LBS	3.55	5.00	4.05
3430	813-A003	Concrete Railing, 42"	1,480.000	LF	206.60	200.00	217.35
3440	815-A007	Loose Riprap, Size 300	6,937.000	TON	121.70	125.00	128.23
3450	815-E001	Geotextile under Riprap	6,383.000	SY	2.70	6.00	5.12
3460	907-803-I002	PDA Test Pile, Concrete Pile	2.000	EA	10,230.00	15,000.00	13,781.27
3470	907-803-I003	PDA Test Pile, HP Steel Pile	23.000	EA	8,542.25	15,000.00	13,511.05
3480	907-803-I004	PDA Test Pile, Steel Pipe Pile	2.000	EA	34,280.00	50,000.00	33,777.62
3490	907-803-J001	Pile Restrike	27.000	EA	2,923.50	3,000.00	3,377.76
3500	907-804-A001	Bridge Concrete, Class BDX	1,668.000	CY	1,700.75	2,400.00	1,688.88
3510	907-804-A002	Bridge Concrete, Class AA	882.000	CY	1,643.00	2,250.00	1,688.88
3520	907-804-A003	Bridge Concrete, Class B	4,726.000	CY	829.40	1,300.00	675.55
3530	907-823-A001	Preformed Joint Seal, Type I	642.000	LF	87.50	35.00	38.77